

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-097-21,265-00-00

LEASE NAME Barrett

WELL NUMBER 1

4620 Ft. from S Section Line

4620 Ft. from E Section Line

SEC. 10 TWP. 27S RGE. 19 ~~XXX~~ (W)

COUNTY Kiowa

Date Well Completed 1/25/89

Plugging Commenced 10/20/04

Plugging Completed 10/22/04

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR TGT Petroleum Corp.

ADDRESS 7570 W. 21st-Bldg. 1010-D, Wichita, Ks. 67205

PHONE#(316) 773-2266 OPERATORS LICENSE NO. 5118

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on _____ (date)

by Steve Pfeifer (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Lansing-KC Depth to Top _____ Bottom _____ T.D. 5,000'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	410'	None
				5 1/2"	4635'	2410'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

Set 5 sack cement on top of sand plug @ 4290'; set plug @ 1250'/w/12 sacks gel & 100# hulls & 50 sacks cement; set plug @ 440'/w/50 sacks cement & 100# hulls; plug @ 40' and fill to top/w/25 sacks cement. All cement 60/40 Posmix.
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor TGT Petroleum Corp. License No. 5118

Address 7570 W. 21st-Bldg. 1010-D, Wichita, Ks. 67205

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: TGT Petroleum Corp.

STATE OF Kansas COUNTY OF Sedgwick, ss.


B. Lynn Herrington

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) B. Lynn Herrington

(Address) 7570 W. 21st-Bldg. 1010-D, Wichita, Ks

RECEIVED
NOV 18 2004
KCC WICHITA



SUBSCRIBED AND SWORN TO before me this 9th day of November, 20 04

Judith K. Moser Notary Public

My Commission Expires: May 17, 2005