

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-097-01,012-00-02

LEASE NAME Brensing "B" OWWO

WELL NUMBER 5

3300 Ft. from S Section Line

4620 Ft. from E Section Line

SEC. 27 TWP. 27 SRGE. 19 ~~18~~ (W)

COUNTY Kiowa

Date Well Completed 4/22/88

Plugging Commenced 11/02/04

Plugging Completed 11/04/04

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR TGT Petroleum Corporation

ADDRESS 7570 W. 21st-Bldg. 1010-D, Wichita, Ks. 67205

PHONE# (316) 773-2266 OPERATORS LICENSE NO. 5118

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on _____ (date)

by Steve Pfeifer (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Cherokee Depth to Top _____ Bottom _____ T.D. 4913

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	320'	None
				5 1/2"	4908'	2697'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

Set 5 sack cement on sand plug @ 4378'; set plug at 1250'/w/12 sacks gel, 100# hulls, and 50 sacks cement. Set plug @ 350'/w/100# hulls & 50 sacks cement; set plug @ 40' and fill to top/w/45 sacks cement. All cement was 60/40 Posmix.
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor TGT Petroleum Corp. License No. 5118

Address 7570 W. 21st-Bldg. 1010-D, Wichita, Ks. 67205

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: TGT Petroleum Corp.

STATE OF Kansas COUNTY OF Sedgwick, ss.

B. Lynn Herrington (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) B. Lynn Herrington
B. Lynn Herrington, Esq. VP
(Address) 7570 W.21st-Bldg.1010-D, Wichita, Ks.

RECEIVED
NOV 18 2004
KCC WICHITA



SCRIBED AND SWORN TO before me this 10th day of November, 20 04

Judith K. Moser
Judith K. Moser Notary Public

My Commission Expires: 5/17/05