

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
211 NORTH BROADWAY  
WICHITA, KANSAS

15-147-00585-00-00

WELL PLUGGING APPLICATION FORM  
File One Copy

Lease Owner Cities Service Oil Co. Address Bartlesville, Oklahoma  
(Applicant)  
Lease (Farm Name) Templeton Well No. 7  
Well Location NE SE NW 990' North & 330' West of / center Sec. 14 Twp. 5 Rge. (E) - (W) 20  
County Phillips Field Name (if any) Hansen-Ls.KC  
Total Depth 3509' Oil  Gas  Dry Hole   
Was well log filed with application? yes If not, explain: attached

Date and hour plugging is desired to begin as soon as possible  
Plugging of the well will be done in accordance with the Rules and Regulations  
of the State Corporation Commission.

Name of the person on the lease in charge of well for owner \_\_\_\_\_

F. P. McCollum, Cities Service Oil Co. Address Box 175, Logan, Kansas

Plugging Contractor Shull Casing Pulling Co.

Plugging Contractor's License No. \_\_\_\_\_

Address Great Bend, Kansas

Invoice covering assessment for plugging this well should be sent to \_\_\_\_\_

James Porter, Cities Service Oil Co. Address Box 553, Russell, Kansas

and payment will be guaranteed by applicant.

RECEIVED  
STATE CORPORATION COMMISSION

JUN 8 - 1955

James Porter  
Applicant or Acting Agent  
6-7-55

CONSERVATION DIVISION Date  
Wichita, Kansas

69-55

PLUGGING  
WELL SEC 14 T 5 R 20W  
BOOK PAGE 125 LINE 19

15-147-00585-00-00

WELL RECORD

Company-Cities Service Oil Co. Well No. 7 Farm-Templeton

Location: 990' North and 330' West of Center Sec 14, T-5, R-20W

Elevation;2099 (2096 Gr.) County-Phillips State-Kansas

Drlg. Comm. February 11, 1950 Contractor-R. W. Rine Drlg. Co.

Drlg. Comp. February 24, 1950 Acid - 1000 gal. 3228-35 (3-19-50)

T.D.-3509 PBTB-3257' Initial Prod.-Physical potential: 205 oil, 15% wtr, 24 hrs. (4-6-50)

CASING RECORD:

8-5/8" @ 205' cem. 250 sx cement  
5-1/2" @ 3503' cem. 150 sx cement

Set Lane-Wells plug at 3477; dumped two gals rock on plug; PBTB 3475 SLM.

FORMATION RECORD:

clay & sand 9-80  
shale & lime 205  
shale & sand 1595  
anhydrite 1635  
red bed, shale & shells 2560  
lime & shale 3020  
lime 3140  
lime & shale 3275  
lime 3490  
lime & shale 3508  
3508 RTD = 3505 SLM

Perf. 31 shots 3411-20  
Perf. 36 shots 3374-85  
Perf. 34 shots 3312-21  
Perf. 32 shots 3299 1/2-3308

3/2/50 Acidized 1500 gal. 3374-85 and 3411-20.

Pumped 139 water, trace oil, 13 hrs.

Set retainer at 3284 and squeezed with 100 sx cement; 90 sx through perforations 3299 1/2-3420 at 2000#.

Drl'd cement to 3370 SLM.

Perf. 44 shots 3312-21  
Perf. 42 shots 3299 1/2-3308

3/11/50 Acidized 1500 gals. 3299 1/2-3321  
3/13/50 Pumped 40 wtr., trace oil, 24 hrs.

Set Lane-Wells plug at 3294; dumped 3 gals. rock on plug; PBTB 3292' SLM

perf. 41 shots 3275-85; 300' wtr in 3 1/2 hrs.  
875' wtr in 18 1/2 hrs.

Set Lane-Wells plug at 3269; dumped 3 gals rock on plug; PBTB 3266 SLM

Perf. 28 shots 3210-17, no show.  
Perf. 28 shots 3228-35; 1330' oil and 4 gals wtr in 14 hrs.

Pumped 51 oil, no water, 12 hrs.  
Dumped 2 sx cement on plug; PBTB 3257 SLM

3/19/50 Acidized 1000 gals 3228-35'.

corr. Top Lansing 3227'  
Corr. Top Conglomerate 3498'  
Corr. Top Arbuckle 3502'  
Penetration 7'  
Total depth 3509'

Fillup from Arbuckle

65' oil in 1 hr. 20 mins. at 3507'  
75' oil in 2 hrs. 20 mins. at 3507'  
180' oil in 3 hrs. 20 mins. at 3509'  
225' oil in 3 hrs. 50 mins. at 3509'

2/25/50 Acidized 1000 gals.  
2/28/50 Pumped 18 oil, 10 water, 24 hrs. (Arbuckle)  
5/15/53 Drl'd plug & C.O. to 3509' SLM set packer & produce Arb. 11 oil-10 wtr-24 hrs.  
7/14/53 Acidize Arbuckle w/500 gal.

SYFO: 500 ' 0°  
1000' 1°  
1500' 1°  
2260 1°  
2550' 1°  
3000' 0°

7-7/8" rotary hole

PLUGGING  
SEC 14 T 5 R 20W  
BOOK PAGE 125 LINE 19

6-9-55



15-147-00585-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
~~REGISTRATION DIVISION~~  
WICHITA 2, KANSAS

211 N. Broadway

June 9, 1955

Well No.	7
Lease	Templeton
Description	NE SE NW 14-5-20N
County	Phillips
File No.	125-19

Cities Service Oil Co.  
Box 553  
Russell, Kansas

Gentlemen:

This letter is your authority to plug the above subject well, in accordance with the Rules and Regulations of the State Corporation Commission. When you are ready to plug this well, please contact our District Plugging Supervisor, Mr. Elton Petty, Box 326, Hays, Kansas.

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION

BY:

  
J. P. ROBERTS

cc: District Plugging Supervisor