

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 2/89

WELL PLUGGING APPLICATION FORM

(File One Copy)

15-147-19118-00-03

API Number 11-13-43 (of this well). (This must be listed; if no API# was issued, please note drilling completion data.)

WELL OWNER/OPERATOR OXY USA INC. OPERATORS LICENSE NO. 5447

ADDRESS P. O. Box 26100 Oklahoma City, OK 73126-0100 PHONE # (405) 749-2000
330' FSL

LEASE/FARM Templeton "A" WELL NO. 3W WELL LOCATION 4950' FEL COUNTY Phillips

SEC. 14 TWP. 5S RGE. 20 (~~N~~ or (W) Total Depth 3697' PLUG BACK TD 3355'

CHECK ONE:

OIL WELL GAS WELL D & A SWD OR (INJ) WELL DOCKET NO. E-17,919

SURFACE CASING SIZE 8-5/8" SET AT 175' CEMENTED WITH 125 SACKS

CASING SIZE 5-1/2" SET AT 3526' CEMENTED WITH 150 SACKS

PERFORATED AT 3224-3332'

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Refer to attached procedure.

(If additional space is needed use back of form.)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? No
(If not explain.)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN: 7-7-90

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

J. D. Hininger PHONE # (913) 674-2182
ADDRESS OXY USA INC., P.O. Box 38, Hill City, Kansas 67642

PLUGGING CONTRACTOR J. W. Gibson Well Service

LICENSE NO. 5866

ADDRESS Logan, Kansas 67646

PHONE # (913) 689-7573

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.

SIGNED: Philip W. Pringle
(Operator or Agent)

RECEIVED
STATE CORPORATION COMMISSION

JUN 8 1990
06-08-90
CONSERVATION DIVISION
Wichita, Kansas

DATE: June 7, 1990

4



MEMORANDUM
OCCIDENTAL OIL AND GAS

Wichita, Kansas
June 8, 1990

15-147-19118-00-03

TO: Mr. M. D. Harrison

FROM: Philip W. Pringle

SUBJECT: PLUGGING PROCEDURE.....TEMPLETON "A" #3W
330' FSL - 4950' FEL
SEC 14-5S-20W
PHILLIPS COUNTY, KANSAS

WELL DATA

8-5/8" casing @ 175' w/ 125 sx
5-1/2" casing @ 3526' w/ 150 sx
Perfs: 3224-3332' (6 sets)
PBSD 3355'
FU @ 3330'

* Holes in casing 2797-2828' & 1342-73'

FORMATION DATA

Dakota 685'
Cheyenne Base 1040'
Anhydrite 1600'

STATE OF KANSAS RECEIVED
JUN 8 1990
CONSERVATION DIVISION
Wichita, Kansas

1. Contact the KCC District Office #4, Hays, KS, (913) 628-1200, for final approval of plugging project.
2. Pull tubing and packer.
3. Run in perforating gun and shoot 4 SPF at 1590' & 1040'.
4. Run 2" workstring to bottom and spot 50 sx common cement w/ 2% CC. Pull tubing, filling 5-1/2" casing to surface with approximately 300 sx 65/35 cement w/ 6% gel. (Use hulls as needed).
5. Tie onto the 5-1/2" and attempt circulation. If needed tie onto the 8-5/8" and pump 100 sx same cement down casing annulus filling to surface.
6. Let cement set 48 hours, check TOC and cap well.

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

COPY

Company- CITIES SERVICE OIL CO.
Farm- Templeton No. 3

SEC. 14 T. 5 R. 20W
SW SW SW
330' N 330' E SW cor.

Total Depth. 3697'

DEEPENING RECORD

Comm. 10-29-43


Comp. 11-14-43

County Phillips
KANSAS

Shot or Treated.

Contractor. R.W. RINE DRIG. CO.

Issued. 3-29-58



Elevation. 2108'

Production. SWDN

CASING:
8 1/8" 175' cem. 125'
5 1/2" 3526' cem. 150'

sand, clay, shale 0-80
lime 175
shale 1080
sand 1150
shale, red rock 1400
shale, sand 1600
anhydrite 1633
shale 1920
shale, lime 2115
shale shells 2285
shale 2515
shale, lime 2630
shale 2690
shale, shells 2480
shale 2920
shale, lime 2955
lime 3432
shale 3452
shale, lime 3510
lime 3527
cored lime (rec. 3') 3530
3530 RTD. - 3527 SIM
lime 3535
dolomite, shale red 3565
lime 3580
Total Depth

Figures indicate Bottom of Formations.
148' of 4 1/4" liner @ 3579' cem.
with 50 sx cem.

Old Total Depth 3580
lime 3648
sand 3690
Granite Wash 3697
Total Depth

TOPS:
Eros. Arbuckle 3490
Arbuckle 3521
Reagan 3648
Granite Wash 3690
Pen. 7

Input 10 bbls. WPH natural.
Acid 1500 gals. 10-27-50

Corr. TOPS:
Gorham 3483
Eros. Arbuckle 3490
Arbuckle 3521
Pen. 59

K. G. S. LIBRARY

STATE RECEIVED

JUN 8 1990

CONSERVATION DIVISION
Wichita, Kansas



Kansas Corporation Commission

MIKE HAYDEN GOVERNOR
KEITH R. HENLEY CHAIRMAN
RICH KOWALEWSKI COMMISSIONER
MARGALEE WRIGHT COMMISSIONER
JUDITH McCONNELL EXECUTIVE DIRECTOR
FRANK A. CARO, JR. GENERAL COUNSEL

CONSERVATION DIVISION
SHARI FEIST ALBRECHT, DIRECTOR
200 Colorado Derby Bldg.
202 W. 1st Street
Wichita, KS 67202-1286
(316) 263-3238

THIS NOTICE

SEP 11 1990

EXPIRES

June 11, 1990

NOTICE OF RECEIPT OF
WELL PLUGGING APPLICATION

15-147-19118-00-03

OXY USA INC.
P.O. Box 26100
Oklahoma City, OK 73126-0100

Templeton "A" 3W
330'FSL-4950'FEL
Sec. 14-05-20W
Phillips County

Gentlemen:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office to review your proposed plugging method at least five (5) days before plugging the well.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. The CP-1 is simply reviewed to determine compliance with plugging rules and regulations.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

Shari Feist Albrecht

Shari Feist Albrecht
Director

District: #4 2301 E. 13th
Hays, KS 67601
(913) 628-1200



Kansas Corporation Commission

MIKE HAYDEN GOVERNOR
 KEITH R. HENLEY CHAIRMAN
 RICH KOWALEWSKI COMMISSIONER
 MARGALEE WRIGHT COMMISSIONER
 JUDITH McCONNELL EXECUTIVE DIRECTOR
 FRANK A. CARO, JR. GENERAL COUNSEL

CONSERVATION DIVISION
 SHARI M. FEIST, DIRECTOR
 200 Colorado Derby Bldg.
 202 W. 1st Street
 Wichita, KS 67202-1286
 (316) 263-3238

September 11, 1990

15-147-19118-00-03

NOTICE OF RECEIPT OF WELL PLUGGING EXTENSION REQUEST

OXY USA INC.
 P.O. Box 26100
 Oklahoma City, OK 73126-0100

Templeton "A" 3W
 330' FSL-4950' FEL
 Sec. 14-05-20W
 Phillips County

Gentlemen:

This letter is to notify you that the Conservation Division is in receipt of your request for an extension of time in which to plug the above-captioned well. You are hereby granted an extension of thirty (30) days in which to plug the well.

Please contact the district office listed below to review your suggested method of plugging at least five (5) days before plugging the well (K.A.R. 82-3-113).

This notice is void after thirty (30) days from the above date.

Any additional extension may be granted for good cause only upon written request to this office.

Sincerely,

Shari Feist Albrecht

Shari Feist Albrecht
 Director

District: #4 2301 E. 13th

 Hays, KS 67601

 (913) 628-1200
