

15-147-00135-00-00.

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH


Locate well correctly on above  
Section Plat

Phillips County. Sec. 8 Twp. 5 Rge. 20 (M) (W)  
 Location as "NE/CNW/SW" or footage from lines SW SE SW  
 Lease Owner T. T. Ellsworth & Braden Drilling Co.  
 Lease Name Miller Well No. 1  
 Office Address 814 Union National Bank Bldg.  
 Character of Well (completed as Oil, Gas or Dry Hole) dry  
 Date well completed Jan. 17, 1955 19  
 Application for plugging filed Jan. 20, 1955 19  
 Application for plugging approved 19  
 Plugging commenced Jan. 17, 1955 19  
 Plugging completed Jan. 17, 1955 19  
 Reason for abandonment of well or producing formation  
dry  
 If a producing well is abandoned, date of last production 19  
 Was permission obtained from the Conservation Division or its agents before plugging was com-  
 menced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty  
 Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3600 Feet  
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	2 1/2	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Set #1 plug @ 220', cemented with 150 sacks cement,  
set #2 plug 35', cemented with 10 sacks cement to bottom  
of cellar.

(If additional description is necessary, use BACK of this sheet)  
 Name of Plugging Contractor Braden Drilling Co.  
 Address 814 Union National Bank Bldg.

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
Louis E. Potucek (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Louis E. Potucek  
814 Union National Bank Bldg., Wichita, Kansas  
 (Address)

SUBSCRIBED AND SWORN TO before me this 20th day of January, 1955  
Norma Richer Notary Public.

My commission expires April 29, 1957

PLUGGING  
 FILE SEC 8 T 5 R 20W  
 BOOK PAGE 92 LINE 8

1-21-55

MILLER #1

Operator: T. T. Ellsworth & Braden Drilling Co.

SW SE SW  
8-5-20W  
Phillips Co., Kansas

Contractor: Braden Drilling Co.

Test Commenced: 1-8-55  
Test Completed: 1-17-55

Casing Record: Set 241' of 8-5/8" casing with 175 sacks cement.

Surface clay	241
Shale	412
Shale & shells	1630
Anhydrite	1685
Lime & shale	2540
Lime	3270
Lime & shale	3328
Lime	3508
Lime & shale	3538
Lime	3600 T. D. R. B.

STATE OF KANSAS,)  
(SS:-  
SEDGWICK COUNTY,)

I hereby certify that the above information is true and correct as revealed by the records of the Braden Drilling Company.

Renald Patrick

Subscribed and sworn to before me this 20th day of January, 1955.

Norma Risher  
Notary Public

My commission expires April 29, 1957.

PLUGGING  
FILE SEC- 8 T 5 R 20W  
BOOK PAGE 92 LINE 8

1-21-55