

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-147-00460-00-00

API NUMBER 5/8/53

LEASE NAME Hansen F

WELL NUMBER 1

SPOT LOCATION 330' S-990' W

SEC. 15 TWP. 5 SRGE. 20 (E) or (W)

COUNTY Phillips CO

Date Well Completed 5/8/53

Plugging Commenced 6/13/84

Plugging Completed 6/14/84

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Cities Service Oil & Gas Corp.

ADDRESS 3545 NW 58th Street Oklahoma City, OK 73112

PHONE # (405) 949-4256 OPERATORS LICENSE NO. 5447

Character of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District #6, Hays, KS

Is ACO-1 filed? No If not, is well log attached? Yes

Producing formation 3534-3537 Depth to top 3527 bottom 3537 T.D. 3557

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	5/8/53	
				5-1/2"	5/8/53	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. 5 1/2 CSG @ 3530'. 7' - OH, State Plugger, Dennis Hamel. Pumped down 5 1/2" w/50 sacks of 50/50 Pozmix + 8% Gel + 3% cc, 20 sacks gel, 5 1/2 wiper, plug 100 sacks 50/50 Poz. Pumped down 8 5/8" 5 sacks gel w/25 sacks hulls + 150 sacks 50/50 Doz mix. Cut casing off and capped.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton Services License No. _____

Address 1100 E 8th Street, Hays, KS 67601

STATE OF KS COUNTY OF Sedgwick, ss.


Charles N Richmond (employee of operator) or
(operator) of above-described well, being first duly sworn on oath, says: That
I have knowledge of the facts, statements, and matters herein contained and
the log of the above-described well as filed that the same are true and
correct. Help me God.

(Signature) Charles N. Richmond

(Address) Charles N. Richmond
800 Sutton Place
Wichita KS, 67202

*Received
8-20-84
KCC
MS*

SUBSCRIBED AND SWORN TO before me this 15th day of August, 1984



Lodema A. Stoneroad
Notary Public
Lodema A. Stoneroad

WELL RECORD 15-147-00460-00-00

Lease Hansen "A" Well No. 1 S. 15 T. 5 R. 20W
County Phillips State Kansas Elev. 2122 (2120 Gr)
Location 330' South and 990' West of E/4 Cor.
Dr. Commenced April 26, 1953 Dr. Completed May 8, 1953
Drilled By R. W. Rine Drilling Co. T. D. 3537'
Acid 500 gals. 5-11-53
Initial Prod. 87 oil, 38 water, 24 hrs. (5-13-53)

Casing Record

8-5/8" 3 200' cem. w/ 200 sx cement
5-1/2" 3 3530' cem. w/ 150 sx cement

Corr. Heebner 3223'
Corr. Dodge 3245'
Corr. Lansing 3266'
Corr. Gorham Sand 3518'
Corr. Arbuckle 3527'
Penetration 10'
Total Depth 3537'

Good show oil at 3534'.
91 gals. oil in 1 1/2 hrs. at 3537'.
332' oil and 130' water in 12 hrs.

SYFO: 500' 1°
1000' 1°
1500' 1°
2000' 2°
2500' 1°

7-7/8" rotary hole.