

15-147-20088-00-00

API NUMBER NA  
LEASE NAME Wiltrout  
WELL NUMBER 1

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

2970 Ft. from S Section Line  
2970 Ft. from E Section Line

LEASE OPERATOR Bard Oil Co. Inc  
ADDRESS Box 428 Logan KS 67646  
PHONE# (913) 689-7456 OPERATORS LICENSE NO. 5352

SEC. 18 TWP. 5 RGE. 20 (E) or (W)  
COUNTY Phillips

Character of Well oil  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Date Well Completed 3-20-70  
Plugging Commenced 12-14-95  
Plugging Completed 12-14-95

The plugging proposal was approved on 12-11-95 (date)  
by Dennis Hamel (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? \_\_\_\_\_

Producing Formation KC Depth to Top 3422 Bottom 3460 T.D. 3557

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
<u>sand + shale</u>	<u>wtr</u>			<u>8 5/8</u>	<u>207</u>	<u>None</u>
<u>KC</u>	<u>oil + wtr</u>			<u>4 1/2</u>	<u>3556</u>	<u>None</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.  
Pumped down 4 1/2 casing with 25 SKS cement with 200# Halls; then 10 SKS of gel followed by 150 SKS cement with 200# of Halls. 500# max. pres and 300# shut-in  
Pumped down Annulus with 25 SKS cement with 100# of Halls. 100# shut-in  
(If additional description is necessary, use BACK of this form.)


Name of Plugging Contractor Allied Cementing License No. \_\_\_\_\_  
Address P.O. Box 31 Russell, KS 67665 12-18-95

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Bard Oil Co. Inc

STATE OF KS COUNTY OF Phillips

Jim R. Bard (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jim R. Bard  
(Address) P.O. Box 428 Logan, KS 67646



DEB AND SWORN TO before me this 15th day of December, 19 95  
Marilyn J. Whitsitt  
Notary Public

My Commission Expires: 2-9-98

