

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-147-19121-0000

LEASE NAME Wiltrout A

WELL NUMBER 3 SWD

3170 Ft. from S Section Line

1431 Ft. from E Section Line

SEC. 18 TWP. 5S RGE. 20 ~~(E)~~ or (W)

COUNTY Phillips

Date Well Completed 6/6/75

Plugging Commenced 9/21/87

Plugging Completed 9/21/87

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Cities Service Oil and Gas Corporation

ADDRESS 3545 NW 58th Street, Oklahoma City, OK 73112

PHONE# (405) 949-4432 OPERATORS LICENSE NO. 5447

Character of Well SWD

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? District #4

Is ACO-1 filed? yes If not, is well log attached? yes

Producing Formation Arbuckle Depth to Top OH 3529' Bottom 3625' T.D. 3731'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put in | Pulled out |
|-----------|---------|---------|------|---------|--------|------------|
| Arbuckle | --- | OH 3529 | 3625 | 10 3/4" | 1673' | 0' |
| | | | | 6 5/8" | 3529' | 0' |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set.
Mixed & dumped 500 sx HDL cmt & 10 sx hulls down 6 5/8" csg; pumped in additional 5 sx.
Mixed & pumped 20 sx HDL cmt containing 1/4# Flo down csg annulus. Cmt circulated up 6 5/8" csg. Well P & A. State Witness: Mr. Dennis Hamel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton Cement Co. License No. _____

Address Oberlin, Kansas

STATE OF Oklahoma COUNTY OF Oklahoma, ss.

Del G. Oliver, Engineering Manager (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Del G. Oliver

(Address) 3545 NW 58th Street

Oklahoma City, Oklahoma 73112

SUBSCRIBED AND SWORN TO before me this 6th day of November 19 87

My Commission Expires: 4-24-89

Jessie Jo Stewart
Notary Public
NOV 18 1987
11-18-87
Form CP-
CONSERVATION DIVISION Revised 08-8.
Wichita, Kansas

DRILLERS LOG

No. 3 Wiltrout SWD "A"

CASING RECORD:

10-3/4" @ 1673'
w/950 sx. cmt.

6-5/8" @ 3529'
w/450 sx. cmt.

TOTAL DEPTH: 520'

COMPANY: Cities Service Oil Company

CONTRACTOR: Red Tiger Drilling Company

COMMENCED: 5-25-75

COMPLETED: 6-6-75

DESCRIPTION: 3170 ^{KCC}
1431' FEL 530' FSL ^{ayB}
of NE/4
18-5S-20W
Phillips County,
Kansas

ELEVATION:

| <u>FORMATION</u> | <u>FROM</u> | <u>TO</u> | <u>REMARKS</u> |
|----------------------|-------------|-----------|----------------|
| Surface Clay & Shale | 0 | 525 | |
| Shale & Clay | 525 | 950 | |
| Shale | 950 | 1120 | |
| Sand | 1120 | 1326 | |
| Shale | 1326 | 1597 | |
| Argilliferous | 1597 | 1633 | |
| Shale & Sand | 1633 | 1665 | |
| Shale | 1665 | 2725 | |
| Shale | 2725 | 2917 | |
| Shale | 2917 | 3025 | |
| Shale | 3025 | 3145 | |
| Shale | 3145 | 3625 | |
| Shale | 3625 | 3675 | |
| Sand | 3675 | 3721 | |
| Shale | 3721 | 3729 | |

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

Linda H. Dickens
Linda H. Dickens

Subscribed and sworn to before me this 6th day of July, 1975.

D'Ann Drennan
Notary Public

My Commission Expires:

9th day of July, 1977

