

15-147-00142-00-00

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
* Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas


WELL PLUGGING RECORD

Phillips

County. Sec. 18 Twp. 5 Rge. 20 (E) (W)est

Location as "NE/CNW/SW" or footage from lines SW NW NE
Lease Owner R. W. Shields
Lease Name State Well No. 1
Office Address Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed 7-17 19 59
Application for plugging filed 19
Application for plugging approved 7-7 19 61
Plugging commenced 7/11/61 19
Plugging completed 7/13/ 19 61
Reason for abandonment of well or producing formation oil exhausted.

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production September 19 60.
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes.

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation Lansing - Kansas City Depth to top 3266' Bottom 3454' Total Depth of Well 3555' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	208.71' (10 jts)	-0-
				5-1/2" @	3452' (106 jts)	2675

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.
Set plug at 3200 ft. filled up 25 ft. of sand dumped 4 sacks cement Pumped in 40 sacks mud at 550 ft. and 20 sacks cement. Pulled pipe to 180 ft. pumped in 20 sacks cement. Pulled pipe bailed hole to 40 ft. Set 10 ft. rock bridge. Dumped in 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

AUG 1 1961

CONSERVATION DIVISION
Wichita, Kansas

8-1-61

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Central Pipe Pulling Co.
Address 1416 Coolidge, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Norman J. Shields (employee of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Norman J. Shields
Norman J. Shields
308 Rule Bldg. - Wichita 2, Kansas.
(Address)

SUBSCRIBED AND SWORN TO before me this 31st day of July, 19 61.

My commission expires November 26th, 1964.

Nell McComb Notary Public.



WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


15-147-00142-00-00

Company- R. W. SHIELDS & C-G DRILLING CO.
Farm- States No. 1

SEC. 18 T. 5 R. 20W
SW NW NE

Total Depth. 3555'
Comm. 7-8-59 Comp. 7-17-59
Shot or Treated.
Contractor. C-G Drlg.
Issued. 10-31-59

County Phillips
KANSAS



Elevation. 2070' KB

Production. 177 BOED

CASING:

8 5/8" 208.71'
5 1/2" 3452'

Meas. from top of RB.

Figures Indicate Bottom of Formations.

sand-shale	208
shale-sand	1185
sand-shale	1430
red bed	1625
Anhydrite	1661
shale-shell	2228
lime-shale	3063
lime	3507
Arbuckle	3555
Total Depth	

TOPS: K.B.	
Anhydrite	1625
Heebner	3223
Toronto	3249
Lansing	3266
Base Kansas City	3454
Arbuckle	3507

DST #1 3231-94', op 1 1/2 hrs., weak blow thruout test. Shut in 20 mins., rec. 45' oil 60' HOCM, 30' OCM. FP 0-100#, BHP 1060#.

DST #2 3367-97', op 1 hr., weak blow for 4 mins., shut in 20 mins., rec. 12' mud w/few specks of oil. FP 0-0#. BHP 440#/still climbing.

DST #3 3411-53', op 1 hr., weak blow for 7 mins., shut in 20 mins., rec. 5' mud. BHP 0#.