

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-147-00872-00-00

API NUMBER 15-N/A

LEASE NAME Pinkerton A

WELL NUMBER 6

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to  
Cons. Div. Office within  
30 days.

330 Ft. from S Section Line

4950 Ft. from E Section Line

LEASE OPERATOR OXY USA Inc.

SEC. 29 TWP. 5S RGE. 20 (X) or (W)

ADDRESS P. O. Box 26100

COUNTY Phillips

PHONE# (405) 749-2309 Operators License #5447

Date Well Completed 5/4/42

Character of Well Oil

Plugging Commenced 10/14/94

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 10/14/94

The plugging proposal was approved on 9/2/94 (date)

by Dennis Hamel (KCC District Agent's name).

Is ACO-1 filed? No If not, is well log attached? No

Producing Formation Reagan Depth to Top 3595 Bottom 3604 T.D. 3604

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled Out
Reagan	Oil	3595	3604	8 5/8"	153'	
				5 1/2"	3595'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.

Mixed & pumped 25 sks 60/40 POZ w/10% added gel 1/4# Flocele & 150# hulls, followed by 125 sks gel. Followed 175 sks cmt w/250# hulls. Pumping press 1000# shut in press 700#. Hooked up to 8 5/8" surface csq. Pumped 25sks 60/40 POZ w/10% added gel 1/4# sk Flocele & 100# hulls. Pumping press 200# Shut in press 100#.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton Services License No. 5988

Address O.O. Box 47, Oberlin, KS 67749 (800) 437-4751

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: OXY USA Inc.

STATE OF OKLAHOMA COUNTY OF OKLAHOMA, ss.

Jerry Ledlow (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) \_\_\_\_\_

(Address) P. O. Box 26100, OKC, OK 73126-0100

SUBSCRIBED AND SWORN TO before me this 1<sup>st</sup> day of November, 19 94

Ray Ann Kilmer  
Notary Public

My Commission Expires: 5-2-98

STATE OF KANSAS RECEIVED  
CORPORATION COMMISSION  
NOV 03 1994  
Form CP-4  
Revised 05-88  
WICHITA, KANSAS  
11-3-94