

15-147-00970-00-00

Well was completed on:  
 API NUMBER 2-1-1941

LEASE NAME Noel A

WELL NUMBER 1

318 Ft. from S Section Line  
990 Ft. from E Section Line

SEC. 29 TWP. 5S RGE. 20 (E or W)

COUNTY Phillips

Date Well Completed 2-1-1941

Plugging Commenced 4-13-1989

Plugging Completed 4-13-1989

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR OXY USA Inc.

ADDRESS P. O. Box 26100, Oklahoma City, OK 73126-0100

PHONE#(405) 749-2471 OPERATORS LICENSE NO. 5447

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on January 18, 1989 (date)

by Mr. Dale Balthazor of District #4 (KCC District Agent's Name).

Is ACO-1 filed? Well was completed on: 2-1-1941 If not, is well log attached? yes

Producing Formation LKC & Arbuckle Depth to Top 3368 Bottom 3476 T.D. 3602'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

RECEIVED  
 STATE CORPORATION COMMISSION  
 4-27-89  
 APR 27 1989  
 CONSERVATION DIVISION  
 Wichita, Kansas

Formation	Content	From	To	Size	Put in	Pulled out
LKC & Arbuckle	Oil	3368	3476	10-3/4"	155'	0
				5-1/2"	3585'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Ran in hole & perf. 5-1/2" csg. at 1730' & 950' w/3 SPF. Tied onto the 5-1/2" csg. filling to surf. w/330 sx 65/35 poz. w/8% gel + 350# hulls. Pumped down the csg. annulus 120' sx same cmt. + 150 hulls filling it to surface. State Witness: Mr. Dale Balthazor. P&A completed.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton Oil Service Co. License No. \_\_\_\_\_

Address Oberlin, Kansas 67749

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: OXY USA Inc.

STATE OF Oklahoma COUNTY OF Oklahoma, ss.

Bryan Humphries (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Bryan Humphries

(Address) P. O. Box 26100, OKC, OK 73126-0100

SUBSCRIBED AND SWORN TO before me this 25th day of April, 19 89

Marsha B. Wilson  
 Notary Public

My Commission Expires: 4-1-92