

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-147-00548-00-00

Well was completed on:  
API NUMBER 6-9-1948

LEASE NAME Wallgren A

WELL NUMBER 3

2640 Ft. from S Section Line

1650 Ft. from E Section Line

SEC. 29 TWP. 5S RGE. 20 (W)

COUNTY Phillips

Date Well Completed 6-9-1948

Plugging Commenced 1-27-1989

Plugging Completed 1-27-1989

LEASE OPERATOR OXY USA Inc.

ADDRESS P. O. Box 26100, Oklahoma City, OK 73126-0100

PHONE#(405) 749-2000 OPERATORS LICENSE NO. 5447

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on January 6, 1989 (date)

by Mr. Dennis Hamel of Dist. #4 (KCC District Agent's Name).

Is ACO-1 filled? Well was completed on: 6-9-1948 If not, is well log attached? yes

Producing Formation Lansing-KC  
Arbuckle Depth to Top 3340 Bottom 3622 T.D. 3681  
Reagan

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation  | Content | From | To   | Size   | Put in | Pulled out |
|------------|---------|------|------|--------|--------|------------|
| Lansing-KC | Oil     | 3340 | 3622 | 8-5/8" | 163'   | 0          |
| Arbuckle   | Oil     |      |      | 5-1/2" | 3681'  | 0          |
| Reagan     | Oil     |      |      |        |        |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Ran in well & perf. Anhydrite at 1750 & Dakota formation at 950 w/2 SPF. Tied onto the 5-1/2" csg. & filled to surf. w/ 200 sx 65/35 Poz. w/10% gel + 2% ecolite & 10 sx of hulls. Connected onto the 8-5/8" surf. csg. & filled the annulus to surf. w/ 50 sx cmt. & 4 sx of hulls. State Witness: Mr. Dennis Hamel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Ostrom Well Service Inc.

Address Route 1, Box 368, Plainville, KS 67663

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: OXY USA Inc.

STATE OF Oklahoma COUNTY OF Oklahoma

Bryan Humphries (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Bryan Humphries

(Address) P. O. Box 26100, OKC, OK 73126-0100

SUBSCRIBED AND SWORN TO before me this 2nd day of February, 19 89

Marsha G. Wilson  
Notary Public

My Commission Expires: 4-1-92

RECEIVED  
STATE CORPORATION COMMISSION

FEB 6 1989

2-6-89  
CONSERVATION DIVISION  
Wichita, Kansas