

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-147-19114-00-01

API NUMBER 15-N/A

LEASE NAME Noel A

WELL NUMBER 4

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to  
Cons. Div. Office within  
30 days.

990 Ft. from S Section Line

1650 Ft. from E Section Line

SEC. 29 TWP. 5S RGE. 20 (X) or (W)

COUNTY Phillips

Date Well Completed 9/15/48

Plugging Commenced 11/3/94

Plugging Completed 11/3/94

LEASE OPERATOR OXY USA Inc.

ADDRESS P. O. Box 26100

PHONE# (405) 749-2309 Operators License #5447

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on \_\_\_\_\_ (date)

by Carl Goodrow (KCC District Agent's name).

Is ACO-1 filed? No If not, is well log attached? No

Producing Formation Arbuckle Depth to Top 3596 Bottom 3606 T.D. 3614

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled Out
Arbuckle	Oil	3596	3606	8 5/8"	198'	
				5 1/2"	3610'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.

Perfed @ 1525' & 920' Mixed & pumped 50 sks 60/40 POZ w/10% added gel 1/4# Flocele & 100 # hulls down ann. Shut in press 100#. Mixed & pumped 50sks 60/40 POZ 10% gel 1/4# Flocele & 100# hulls, followed by 125 sks gel, followed by 125 sks 60/40 POZ 10% gel 1/4# Flocele w/250# hulls. Shut in press 300# & holding.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor J. W. Gibson Well Service License No. 5866

Address 505 W. Commercial, Logan KS 67646

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: OXY USA Inc.

STATE OF OKLAHOMA COUNTY OF OKLAHOMA, ss.

Jerry Ledlow (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jerry Ledlow

(Address) P. O. Box 26100, OKC, OK 73126-0100

SUBSCRIBED AND SWORN TO before me this 7th day of November, 19 94

Jerry L. Padilla  
Notary Public

My Commission Expires: 8-21-96

RECEIVED  
STATE CORPORATION COMMISSION

NOV 10 1994 Form CP-4  
Revised 05-88

CONSERVATION DIVISION