

15-147-00506-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-147-05-14-43

LEASE NAME Wallgren "B"

TYPE OR PRINT
NOTICE: Fill out completely
and return to Comm. Div.
office within 30 days.

WELL NUMBER 2

2970 ft. from S Section Line

4950 ft. from E Section Line

SEC. 29 TWP. 05 RGE. 20 or (W)

COUNTY Phillips

Date Well Completed 05/24/43

Plugging Commenced 11/19/96

Plugging Completed 11/19/96

LEASE OPERATOR OXY USA Inc.

ADDRESS P.O. Box 300; Tulsa, OK 74102-0300

PHONE # (918) 561-2211 OPERATOR'S LICENSE NO. 5447

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply)

The plugging proposal was approved on October 22, 1996 (date)

by Dennis L. Hamel

Is ACO-1 file? No If not, is well log attached? Yes

Producing Formation Arbuckle Depth to Top 3589' Bottom 3611' T.D. 3668'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORDS

| Formation | Content | From | To | Size | Put in | Pulled out |
|-----------|---------|-------|-------|--------|--------|------------|
| Arbuckle | Oil | 3598' | 3602' | 8-5/8" | 158' | |
| | | | | 5-1/2" | 3668' | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

Dug out csg and orange peeled 5-1/2" to 8-5/8" csg. Install 2" riser to surface. Rigged up H.L.S. & perf at 1100' and 1750' with 2 spf. MIRU Murfin Drilling, RIH with 2-3/8" tbg. Open ended to 3550'. Pumped 65 sxs MIDCON 2 with 2% CC and 200# cottonseed hulls. Pulled 48 jts to 2100'. Pumped 65 sxs cement & 200# hulls. Pulled tbg to 500'. Pumped 35 sxs cement and circulated to surface. POOH with rest of tbg. (continued on back)

Name of Plugging Contractor Halliburton Energy Services License No. 5287

Address 1102 E. 8th St.; Hays, KS 67601

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: OXY USA Inc.

STATE OF Kansas COUNTY OF Rooks, ss.

Kenneth R. Curry (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


KANSAS CORPORATION COMMISSION

2-18-97
FEB 18 1997

(Signature) [Signature]

(Address) P.O. Drawer D; Plainville, KS 67663

SUBSCRIBED AND SWORN TO before me this 14 day of February, 1997



CONSERVATION DIVISION
WICHITA, KS

Sheryl Axelson
Notary Public

My Commission Expires: May 20, 2000

Additional plugging report information for Wallgren "B" #2

Hooked up to 5-1/2" casing and pumped 20 sxs cement. Max PSI 500. SIP 255 PSI. Hooked up to 8-5/8" csg and pumped 50 sxs MIDCON 2 cement with 2% CC and 100# hulls. Total 235 sxs cement used.