

815-147-00725-11-00

8 041196

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- D-9652 10-17-62

W/2 NE SE, SEC. 18, T 5 S, R 20 W/4E

1980 feet from S section line

990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5447

Lease Name Kowitz Well # 1

Operator: Oxy USA Inc.

County Phillips 120.12

Name & Address Box 26100

Well Total Depth 3696 feet

Okla City, Ok. 73126-0100

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 1683 w/750 sks

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well kxx D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Halliburton Cementing License Number _____

Address Oberlin, Ks

Company to plug at: Hour: 9:00 AM Day: 8 Month: June Year: 19 90

Plugging proposal received from J. D. Hininger

(company name) Oxy USA (phone) _____

were: 5 1/2 casing set at 3592 w/200 sks cement; O. H. 3593592-3696;

Pulled out 1238 of 5 1/2 casing. Holes in 5 1/2 below 1238.

Ordered 100 sks Class A cement plus 600 sks 65/35 poz 8% gel plus hulls.

Plugging Proposal Received by Marion J. Schmidt
Dennis Hamel (TECHNICIAN)

Plugging Operations attended by Agent?: All x Part _____ None _____

Operations Completed: Hour: 12:45 Day: 11 Month: June Year: 19 90

ACTUAL PLUGGING REPORT R. I. H. w/ 2 7/8 tubing; spot 100 sks Class A

cement. Pull tubing to 2675; spot 100 sks 65/35 poz 8% gel w/4 sks hulls; pull tubing

to 1175'; spot 300 sks 65/35 poz 8% gel w/2 sks hulls, pull tubing: June 11, 1990

Run in hole w/tubing to t.o.c. at 713; pumped in 160 sks

cement to circ cement at surf. P.O.O.H. w/tubing; hook up to 8 5/8 casing and set

10 sks cement. Max 300 lbs: S.I. 300 lbs.

Remarks: _____

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE: 8-24-90

INV. NO. 29047

6-11

SEP 14 1990

Signed Dennis L. Hamel
(TECHNICIAN)
Dennis L. Hamel