

4-041735

12-14

API Number: 15-147-20,088

-00-00

TQ:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

SE SE NW /4 SEC. 18, 05 S, 20 W
2970 feet from S section line
2970 feet from E section line

Operator license# 5352

Lease: Wiltout Well # 1

Operator: Baird Oil Company, Inc.

County: Phillips

Address: Box 428
Logan, Kansas 67646

Well total depth 3557 115.60 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 207 feet
w/140 sxs.

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Allied Cementing License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: 8:00 A.M. Day: 14 Month: December Year 1995

Plugging proposal received from: Jim Baird

Company: Baird Oil Company, Inc. Phone: 913-689-7456

Were: 4 1/2" casing set at 3556' w/200 sxs cement. Perf. at 3422' - 3460'. Anhy. at 1675'.
Dakota at 1050'. W.L.M. at 3450'. T.O.F. at 1600'.
Ordered 200 sxs 60/40 pozmix - 10% gel with 1/4# F.C. plus 500# hulls.

Plugging Proposal Received by: Dennis L. Hamel

Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour: 10:15 A.M., Day: 14, Month: December, Year: 1995

Actual plugging report: Perforated casing at 1050' and 1675'. Pumped in 4 1/2" casing: 25 sxs cement with 200# hulls, followed with 10 sxs gel, followed with 150 sxs cement with 200# hulls. Max. P.S.I. 500#. S.I.P. 300#. Pumped down 8 5/8" S.P. with 25 sxs cement with 100# hulls in cement. Max. P.S.I. 200#.

STATE CORPORATION COMMISSION

DEC 28 1995

12-26-95

Remarks:
Condition of casing(in hole): GOOD X BAD
Bottom plug(in place): YES X, CALC X, NO
Plugged through TUBING, CASING X. Elevation: GL

I did [X] / did not [] observe the plugging.

Dennis L. Hamel
(agent)

Form CP-2/3

INVOICED

DATE 1-8-96
INV. NO. 44427