

KANSAS

Y
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-147-20110-00-00

RECEIVED
STATE CORPORATION COMMISSION

OCT 27 1970

CONSERVATION DIVISION
Wichita, Kansas

10-27-70

Operator's Full Name H. B. Mabee Company

Complete Address Box 94718 Oklahoma City, Oklahoma

Lease Name Lamb Well No. 1

Location 100' SW of SE NE SW Sec. 16 Twp. 5 Rge. (E) (W) 20

County Phillips Total Depth 3595

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor D. J. Dreiling & Sons

Address Victoria, Kansas License No.

Operation Completed: Hour 12 M Day 24 Month 10 Year 1970

The above well was plugged as follows:

RTD 3595' 8 5/8 csg set at 218' cwc Cmt Mat 50-50 poz W/6% gel.

Gunned pits, circulated heavy mud, set cementing plug at 1100' and displaced 70 sk

cmt thru drill pipe. Heavy mud to 250' set cementing plug and displaced 20 sk cmt

thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to

base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: L. J. Massey
Well Plugging Supervisor

DATE 10/28/70

INV. NO. 2764-W