

15-47-20413-00-00

6 030879

API NUMBER 15- 6-30-83

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

*NATURE*  
CN/2 ~~NE NW~~, SEC. 4, T 5 S, R 20 W/E

*KCCap* 4950 feet from S section line  
~~3300~~ 330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5352

Lease Name Baird Well # 1

Operator: Baird Oil Co. Inc.

County Phillips *111.64*

Name & Address Box 428

Well Total Depth 3435 feet

Logan, Ks. 67646

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 208'

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing License Number 6050

Address Chase, Ks.

Company to plug at: Hour: PM Day: 18 Month: 5 Year: 19 87

Plugging proposal received from Millard Kelso

(company name) Chase, Ks. (phone) \_\_\_\_\_

were: 8 5/8" set at 208" cwc 4 1/2" set at 3417' with 200 sx open hole with perf's at  
3118' - 3394' Plug above ar buckle at 3394' GL 1990' order com sand and cement.  
Shoot and strip pipe - order 150 sx ATL 65/35 pox 10% gel 2% dicel. 5sx hulls  
Allied Cmt. Co.

Plugging Proposal Received by Dale Balthazor and *Carl Goodrow*  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None

Operations Completed: Hour: 12:45 PM Day: 18 Month: 5 Year: 19 87

ACTUAL PLUGGING REPORT sand bottom to 3050' with 4 sx com cmt on sand with bailer.

4 shots at 1817 - 1603 - 1394 - 1364 recovered 1364' of 4 1/2" casing.

Mix and pump down 8 5/8" csg 5sx hulls with 150 sx ATL cmt. Blend Max. PSI

700 # close in at 300 # psi. Plug Complete.

RECEIVED  
STATE CORPORATION COMMISSION

JUL 16 1987 *7-16-87*

Remarks: Plug checked by Dale B. OK  
(If additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION  
Wichita, Kansas

INVOICED  
If you did not observe this plugging.

DATE 7-16-87

Signed *Carl Goodrow*  
(TECHNICIAN)  
Carl Goodrow

INV. NO. 17499