

9-21-87 15-147-19121-00
104,028C
C-17,755

6 040798

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-
SE SW NE, SEC. 18, T 5 S, R 20 W/E
530-3170 KCC OB feet from S section line
1431 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5447

Lease Name Wiltraut Well # 3 SWD
County Phillips 121.26
Well Total Depth 3731 feet

Operator: Cities Service Oil and Gas
Name & Address 3545 NW 58th Street
Oklahoma City, Ok

Conductor Pipe: Size feet
Surface Casing: Size 10 3/4 feet 1673' w/800 +
150 class A

Abandoned Oil Well Gas Well Input Well SWD Well X D&A A
Other well as hereinafter indicated

Plugging Contractor Halliburton Cement Co. License Number
Address Oberlin, Kansas

Company to plug at: Hour: 9:00 AM Day: 21 Month: Sept Year: 19 87

Plugging proposal received from J. D. Heininger
(company name) C. C. (phone) 913-674-2182

were: 6 5/8" F. G. lined set at 3529' w/450 sks cement, (O. H.)
T.O.C. at 2150' Top of fish at 1730' (4 3/4" star bit and jars)
F. G. bridge at 740'; took input rate at 7 - 10 bbls min.
Ordered 550 sks 65/35 Pozmix 10% Gel w/1/4# Flocele plugs, 8 sks Hulls.

Plugging Proposal Received by Dennis Hamel
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None
Operations Completed: Hour: 5:00 PM Day: 21 Month: Sept Year: 19 87

ACTUAL PLUGGING REPORT Pumped in 6 5/8" casing; 200 sks 65/35 Pozmix 10% Gel.
w/1/4# Flocele followed w/325 sks 65/35 Pozmix 10% Gel w/1/4# Flocele plus 8 sks Hulls.
Cement circulated annulus. Max Psi 500#.

RECEIVED
STATE CORPORATION COMMISSION
OCT 9 1987
10-9-87
CONSERVATION DIVISION
WICHITA, KANSAS

Remarks: Cmt. top ck. by D&A B - 26" from surface.
(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

DATE 10-12-87

Signed Dennis L. Hamel
(TECHNICIAN)
Dennis L. Hamel

INV. NO. 18455 c failed mit 7/21/87
09-21 OCT 29 1987 DLS