

6 031216
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

X 1-515-147-20032-06-00
API NUMBER 15- 1968

TECHNICIAN'S PLUGGING REPORT

Operator License #5447
Operator: Oxy USA Inc.
Name & Address: Box 26100
Oklahoma City, Ok. 73126-0100

SEC. 18, T. 5 S, R. 20 W/E
2879 feet from S section line
712 feet from E section line
Lease Name Wiltroat Well # a 2 D SWD
County Phillips 121.03
Well Total Depth 3724 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1625

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well U&A _____

Other well as hereinafter indicated D-14,266

Plugging Contractor Halliburton License Number _____
Address Oberlin, Ks.

Company to plug at: Hour: AM Day: 5 Month: Jan Year: 19 89

Plugging proposal received from Pringle

(company name) Oxy USA (phone) _____

were: 8 5/8" set at 1625' w/750 sks cwc. 5 1/2" cement lined set at 3611' w/200 sks.

Squeezed from 1798' to surface. Perf 3530' - 70' 3582' - 3608'. O.H. 3611' - 28'.
PBTD 3628'. Order 50 sks common cement. 300 sks 60/40 Poz 8% Gel 500# Hulls. Halliburton
Cement Co. OWS Water.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:45AM Day: 5 Month: Jan Year: 19 89

ACTUAL PLUGGING REPORT Ran tubing to 3600' 50 sks common cement

and 2 sks Hulls on bottom w/300 sks cement blend w/3 Hulls to surface. Squeeze 5 1/2" to max
psi 600#. Close in psi 150#. Plug complete.

RECEIVED
STATE CORPORATION COMMISSION

JAN 27 1989

1-27-89

Remarks: (If additional description is necessary, use BACK of this form.)
CONSERVATION DIVISION
Wichita, Kansas

INVOICED observe this plugging.

DATE 2-02-89

INV. NO. 23831

Phil S.

Signed Carl Goodrow (TECHNICIAN)
Carl Goodrow