

4-041473

5-26

15-147-00876-00-00

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15- - 10-29-48

NE NE SW /4 SEC. 29, 05 S, 20 W  
2310 feet from S section line  
2970 feet from E section line

Operator license# 5447

Lease Pinkerton "A" well # 10

Operator: OXY USA, Inc.

County Phillips

Address: 110 S. Main  
Suite #800  
Wichita, Kansas 67202

Well total depth 3627 feet <sup>117.87</sup>  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 184 feet  
w/256 sx.

Aband. oil well X, Gas well    , Input well    , SWD    , D & A    

Plugging contractor: Halliburton Cementing License# -

Address: Oberlin, Kansas

Company to plug at: Hour: 9:00A.M. Day: 26 Month: May Year: 93

Plugging proposal received from: Jim Norwell

Company: OXY USA, Inc. Phone:                     

Were: 5 1/2" casing set @ 3622' w/150 sx. cement. Perf. @ 3605' - 3627'.  
Anhy. 1770' - Dakota @ 1100'.  
Ordered 250 sxs. 60/40 pozmix - 10% gel. with 1/4# F.C. plus 500# hulls.  
Plus 9 sx. gel.

Plugging Proposal Received by: Dennis L. Hamel

Plugging operations attended by agent? All[ X ], Part[     ], None[     ]

Completed: Hour: 1:30P.M., Day: 26, Month: May, Year: 93

Actual plugging report: R.I.H. with tubing to 3550'. Spotted 25 sx.  
cement with 100# hulls. Spotted 9 sx. gel. @ 3200' to 1800'. Pulled  
tubing to 1800'. Spot 110 sx. cement w/200# hulls to circulate at  
surface. P.O.O.H. with tubing and squeezed 50 sx. cement with 100# hulls  
in cement. Max. 300#. Hooked-up to 8 5/8" S.P. Squeezed 50 sx. cement  
w/100# hulls. Max. 300#. Job complete.

Remarks:

Condition of casing(in hole): GOOD X BAD     Anhy. plug: YES X NO      
Bottom plug(in place): YES X, CALC    , NO     Dakota plug: YES X, NO      
Plugged through TUBING X, CASING    . Elevation: 2200 GL RECEIVED

I did X / did not [     ] observe the plugging.

*Dennis L. Hamel*  
STATE CORPORATION COMMISSION  
JUN 30 1993  
(agent) 60-30-93  
Form CP-275 CONSERVATION DIVISION  
Wichita, Kansas

**INVOICED**

JUL 13 1993

DATE                     

INV. NO. 38096