

15-147-00877-00-00

To: <sup>6</sup> 030906  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15955  
SW, SEC. 29, T 5 S, R 20 W/E

TECHNICIAN'S PLUGGING REPORT

1650 feet from S section line  
3630 feet from E section line

Operator License # 5447

Lease Name Pinkerton Well # A 5

Operator: Cities Service Owl and Gas Corp  
Name & Address 3545 N.W. 58 Street  
Oklahoma City, Ok. 73112

County Phillips 119.96

Well Total Depth 3691 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 171

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Halliburton Services License Number \_\_\_\_\_

Address Hays, Kansas

Company to plug at: Hour: AM Day: 18 Month: June Year: 19 87

Plugging proposal received from E. G. Hutchinson

(company name) Cities Service (phone) \_\_\_\_\_

were: 8 5/8 set at 171' w/125 sks. 5 1/2 set at 3691' w/110 sks. Perf 3630' - 40'

5 1/2 csg perforated 4 SPF at 1730' Anhy. and 4 SPF at 1100' DK.

Order 250 sks Econolite 6 sks Hulls Halliburton Cmt. Co.

OWS water trucks.

Plugging Proposal Received by Carl Goodrow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 9:00 AM Day: 18 Month: June Year: 19 87

ACTUAL PLUGGING REPORT

Mix and pump down 5 1/2" csg 55 sks cmt. blend with Hulls mixed in and 50 sks with

Hulls down 8 5/8 - 5 1/2 Annulus w/max Psi. 500# on both and close in Psis of 500#.

Plug complete

Remarks: \_\_\_\_\_  
(If additional description is necessary, use BACK of this form.)

**INVOICED**

DATE 7-21-87

INV. NO. 17544

7-21-87  
REC'D

Signed Carl Goodrow  
(TECHNICIAN)  
Carl Goodrow