

15-147-00849-00-00
-27

108

6 041015

API NUMBER 15-

8-6-1948

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SEC. 29, T 5 S, R 20 W/E
2970 feet from N section line
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5447

Lease Name Wallgren A Well # 4

Operator: Oxy USA Inc.

County Phillips 117.94

Name & Address Box 26100

Well Total Depth 3629 feet

Oklahoma City, Ok. 73126-0100 Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 202' w/250 sks

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Halliburton Cementing License Number

Address

Company to plug at: Hour: 9:00AM Day: 27 Month: Jan Year: 19 89

Plugging proposal received from J.D. Hininger Gene Hutchinson

(company name) Oxy USA (phone)

were: 5 1/2" casing set at 3627' w/150sks. Top perf at 3614' - 21';

Perf anhy at 1750' and base dakota at 940'. Ordered 250 sks 65/35 Poz 10% Gel

2% Lite w/1/4# F.C. plus 5 sks Hulls.

Plugging Proposal Received by Dennis L. Hamel
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 2:00PM Day: 27 Month: Jan Year: 19 89

ACTUAL PLUGGING REPORT Pumped in 5 1/2" casing 155 sks cement w/1/4# F.C. plus 3 sks

Hulls mixed in cement. Max 650# S.I. 300# psi. Pumped in 8 5/8" casing 60 sks cement

w/1/4# F.C. plus 2 sks Hulls mixed in cement. Max 500# S.I. 300# psi.

RECEIVED
STATE CORPORATION COMMISSION

Remarks: (If additional description is necessary, use BACK of this form.) FEB 27 1989 2-27-89

INVOICED serve this plugging.

DATE 3-1-89

INV. NO. 24014

Sub S

Signed Dennis L. Hamel
CONSERVATION DIVISION
Wichita, Kansas
(TECHNICIAN)

Dennis L. Hamel