

6-18-87 15-147-00347-00-00
API NUMBER 15-

To: **6 030909**
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SE _____, SEC. 29, T 5 S, R 20 **(W/E)**

1650 feet from S section line
990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # ~~5447~~

Lease Name Wallgren Well # A 2

Operator: Cities Service Oil and Gas Corp
Name & Address 3545 N. W. 58 Street

County Phillips 117.03

Oklahoma City, Ok. 73112

Well Total Depth 3601 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 5/8 feet 155'

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Halliburton Services License Number _____

Address Hays, Kansas

Company to plug at: Hour: PM Day: 18 Month: June Year: 19 87

Plugging proposal received from E. G. Hutchinson

(company name) Cities Service (phone) _____

were: 8 5/8" set at 155' w/125 sks 5 1/2" set at 3595' w/100 sks open hole.

Perfs. 4 SPF at 1740 Anhy. 4 SPF at 970' Base Dakota + 50'.

Order 250 sks Econolite 65/35 Poz 10% Gel 2% Dical 6 sks Hulls.

Halliburton Cmt. Co. OWS Water Trucks.

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:15 PM Day: 18 Month: June Year: 19 87

ACTUAL PLUGGING REPORT Squeeze down 5 1/2" Csg 153 sks cmt. blend w/5 sks Hulls mixed

in. Max. Psi. 500# close in Psi. 400## Squeeze down 8 5/8" - 5 1/2" Annulus

100 sks. cmt blend w/1 sk Hulls mixed in. Max Psi. 500# close in Psi 500#

Plug complete.

RECEIVED
STATE CORPORATION COMMISSION
7-10-87
JUL 10 1987

Remarks: _____
(If additional description is necessary, use BACK of this form.)

INVOICED (did not) observe this plugging.

DATE 7-10-87

INV. NO. 17466

Signed Carl Goodrow
(TECHNICIAN)

Carl Goodrow