

15-147-005487-00-00  
27

R 103

To: 6 041016  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 6-9-1948  
SEC. 29, T. 5, S. R. 20 W/E  
2640 feet from S section line  
1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 5447

Lease Name Wallgren A Well # 3

Operator: Oxy U.S.A. Inc.  
Name & Address: Box 26100  
Oklahoma City, Ok. 73126-0100

County Phillips 119.63  
Well Total Depth 3681 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 163' w/200 sks

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Halliburton Co. License Number \_\_\_\_\_

Address \_\_\_\_\_

Company to plug at: Hour: 9:00AM Day: 27 Month: Jan Year: 19 89

Plugging proposal received from J. D. Hininger Gene Hutchinson

(company name) Oxy USA (phone) \_\_\_\_\_

were: 5 1/2" casing set at 3681' w/150 sks. Top perf at 3340' - 3622'.

Perf anhy at 1750' and base dakota at 750'.

Ordered 250 sks 65/35 Poz 10% Gel 2% Lite w/1/4" F.C. plus 5 sks Hulls.

Plugging Proposal Received by Dennis L. Hamel  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None

Operations Completed: Hour: 9:25AM Day: 27 Month: Jan Year: 19 89

ACTUAL PLUGGING REPORT Pumped in 5 1/2" casing 200 sks cement w/1/4" F.C. plus 5 sks Hulls.

Max 450# S.I. 300# psi. Pumped in 8 5/8" casing 50 sks cement w/1/4" F.C. plus 1 sk Hulls mixed in cement. Max 500# S.I. 300# psi.

RECEIVED  
STATE CORPORATION COMMISSION

FEB 27 1989 2-27-89

CONSERVATION DIVISION  
Wichita, Kansas

Remarks: (If additional description is necessary, use BACK of Kansas form.)

INVOICED  
observe this plugging.

Signed Dennis L. Hamel  
(TECHNICIAN)  
Dennis L. Hamel

DATE 3-1-89  
INV. NO. 24015