

1-2718-147-00546-00-00

6 041014

API NUMBER 15-12-1942

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

SEC. 29, T. 5 S, R. 20 W  
3630 feet from N X section line  
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5447

Lease Name Wallgren A Well # 1

Operator: Oxy U.S.A. Inc.  
Name & Address: Box 26100  
Oklahoma City, Ok.  
73126-0100

County Phillips 119.75  
Well Total Depth 3623 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 176' w/125

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Halliburton Cementing License Number \_\_\_\_\_

Address \_\_\_\_\_

Company to plug at: Hour: 9:00AM Day: 27 Month: Jan Year: 19 89

Plugging proposal received from J. D. Hininger Gene Hutchinson

(company name) Oxy USA (phone) \_\_\_\_\_

were: 5 1/2" casing set at 3626' w/100 sks. Top perf at 3605' - 20'.  
Perf anhy at 1730' and base dakota at 930'.

Ordered 250 sks 65/35 Poz 10% Gel 2% Lite w/1/4# F.C. plus 5 sks Hulls.

Plugging Proposal Received by Dennis L. Hamel  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None

Operations Completed: Hour: 11:00AM Day: 27 Month: 1 Year: 19 89

ACTUAL PLUGGING REPORT Pumped in 5 1/2" casing 175 sks cement w/1/4# F.C. plus 4  
sks Hulls mixed in cement. Max 500#. S.I. 300# psi. Pumped in 8 5/8" casing 50 sk  
cement w/1/4# F.C. plus 2 sks Hulls mixed in cement. Max 400#. S.I. 300#. psi.

RECEIVED  
STATE CORPORATION COMMISSION

2-27-89  
FEB 27 1989

Remarks: (If additional description is necessary, use BACK CONSERVATION DIVISION  
Wichita, Kansas)

INVOICED

DATE 3-1-89  
INV. NO. 24016

Signed Dennis L. Hamel  
(TECHNICIAN)

Dennis L. Hamel