

11-18 4-041853 15-147-60505-00-00

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15- - 08-04-42

SW SE NW /4 SEC. 29 , 05 S, 20 W  
2970 feet from S section line  
3630 feet from E section line

Operator license# 5447

Lease: Wallgren B Well # 1

Operator: OXY USA, Inc.

County: Phillips 118.69

Address: P.O. Box 300  
Tulsa, Oklahoma 74102-0300

Well total depth 3652 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 10 3/4 Inch @ 169 feet  
w/125 sxs.cmt.

Aband. oil well  , Gas well \_\_\_\_\_, Input well \_\_\_\_\_, SWD \_\_\_\_\_, D & A \_\_\_\_\_

Plugging contractor: Halliburton Cementing, Inc. License# -

Address: Hays, Kansas 67601

Company to plug at: Hour: 7:30 A.M. Day: 18 Month: November Year 1996

Plugging proposal received from: Jim Nowell

Company: OXY USA, Inc. Phone: 918-561-3564

Were: 7" casing set at 3646' w/100 sxs.  
CIBP 3639' - O.H. CIBP at 3643'.  
PSTD 3639'.

Plugging Proposal Received by: Dennis L. Hamel  
Plugging operations attended by agent? All[ ], Part[ X ], None[ ]

Completed: Hour: 11:00 A.M., Day: 18, Month: November, Year: 1996

Actual plugging report: Dug out casing and orange peeled 7" to 10 3/4" casing. Install 2" riser to surface. Rigged up H.L.S. & perf at 1150' and 1800' with 2 spf. MIRU Murfin Drilling, RIH with 2 3/8" tubing. Open ended to 3600'. Pumped 105 sxs MIDCON 2 with 2% CC and 200# cottonseed hulls. Pulled 48 jts. to 2100'. Pumped 105 sxs cement & 200# hulls. Pulled tubing to 600'. Pumped 65 sxs cement and circulated to surface. POOH with rest of tubing. Hooked up to 7" casing and pumped 30 sxs cement. Max. P.S.I. 500#. S.I.P. 275#. Hooked up to 10 3/4" casing and pumped 65 sxs MIDCON 2 cement with 2% CC and 100# hulls. Max. P.S.I. 300#. S.I.P. 200#. Total 355 sxs cement used.

Remarks: Allied Cementing.  
Condition of casing(in hole): GOOD  BAD \_\_\_\_\_ Anhy.plug: YES  NO \_\_\_\_\_  
Bottom plug(in place): YES  , CALC \_\_\_\_\_, NO \_\_\_\_\_ Dakota plug: YES  , NO \_\_\_\_\_  
Plugged through TUBING  , CASING \_\_\_\_\_ Elevation: 2227 K.B.

I did  / did not  observe the plugging.

Dennis L. Hamel  
(agent)

Form CP-2/3

INVOICED  
DATE JAN 13 1997  
INV. NO. 47329