

11-19

4-041854

B-147-00506-0000

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15- - 05-24-53

SW SW NW /4 SEC. 29 , 05 S, 20 W
2970 feet from S section line
4950 feet from E section line

Operator license# 5447

Lease: Wallgren B Well # 2

Operator: OXY USA, Inc.

County: Phillips 119.21

Address: P.O. Box 300
Tulsa, Oklahoma 74102-0300

Well total depth 3668 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 158 feet
w/125 sxs.cmt.

Aband. oil well , Gas well _____, Input well _____, SWD _____, D & A _____

Plugging contractor: Halliburton Cementing, Inc. License# -

Address: Hays, Kansas 67601

Company to plug at: Hour: 11:00 A.M. Day: 19 Month: November Year 1996

Plugging proposal received from: Jim Nowell

Company: OXY USA, Inc. Phone: 918-561-3564

Were: 5 1/2" casing set at 3668' w/125 sxs.
Perfs 3598' - 3602'.
PSTD 3635'.

Plugging Proposal Received by: Dennis L. Hamel 1-10-97

Plugging operations attended by agent? All[], Part[X], None[]

Completed: Hour: 2:00 P.M., Day: 19, Month: November, Year: 1996

Actual plugging report: Dug out casing and orange peeled 5 1/2" to 8 5/8" casing. Install 2" riser to surface. Rigged up H.L.S. & perf at 1100' and 1750' with 2 spf. MIRU Murfin Drilling, RIH with 2 3/8" tubing. Open ended to 3550'. Pumped 65 sxs MIDCON 2 with 2% CC and 200# cottonseed hulls. Pulled 48 jts. to 2100'. Pumped 65 sxs cement & 200# hulls. Pulled tubing to 500'. Pumped 35 sxs cement and circulated to surface. POOH with rest of tubing. Hooked up to 5 1/2" casing and pumped 20 sxs cement. Max. P.S.I. 500#. S.I.P. 255#. Hooked up to 8 5/8" casing and pumped 50 sxs MIDCON 2 cement with 2% CC and 100# hulls. Total 235 sxs cement used.

Remarks: Allied Cementing.

Condition of casing(in hole): GOOD BAD _____ Anhy.plug: YES NO _____
Bottom plug(in place): YES , CALC _____, NO _____ Dakota plug: YES , NO _____
Plugged through TUBING , CASING _____ Elevation: 2176 K.B.

I did[] / did not[] observe the plugging.

Dennis L. Hamel
(agent)

Form CP-2/3

INVOICED

DATE JAN 13 1997

INV. NO. 47328