

11-20 4-041855

15-147-00509-00-00

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15- - 12-09-49

NE SW NW /4 SEC. 29 , 05 S, 20 W
3630 feet from S section line
4290 feet from E section line

Operator license# 5447

Lease: Wallgren B Well # 5

Operator: OXY USA, Inc.

County: Phillips 117.65

Address: P.O. Box 300
Tulsa, Oklahoma 74102-0300

Well total depth 3620 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 206 feet
w/250 sxs.cmt.

Aband. oil well , Gas well _____, Input well _____, SWD _____, D & A _____

Plugging contractor: Halliburton Cementing, Inc. License# -

Address: Hays, Kansas 67601

Company to plug at: Hour: 1:30 P.M. Day: 20 Month: November Year 1996

Plugging proposal received from: Jim Nowell

Company: OXY USA, Inc. Phone: 918-561-3564

Were: 5 1/2" casing set at 3614' w/150 sxs.
Open hole.

Plugging Proposal Received by: Dennis L. Hamel

Plugging operations attended by agent? All[], Part[X], None[]

Completed: Hour: 5:00 P.M., Day: 20, Month: November, Year: 1996

Actual plugging report: Dug out casing and orange peeled 5 1/2" to 8 5/8" casing. Install 2" riser to surface. MIRU Murfin Drilling and RIH with 4 7/8" bit to 275' and cleaned out a bridge. Ran tubing to 1800'. POOH with tubing. Rigged up Mercury wireline and perf at 1110' and 1755' with 2 spf. RIH with 2 3/8" tubing. Open ended to 3600'. Pumped 65 sxs MIDCON 2 with 2% C.C. and 200# Cottonseed hulls. Pulled 48 jts to 2100'. Pumped 65 sxs cement and 200# hulls. Pulled tubing to 600'. Pumped 40 sxs cement and circulated to surface. POOH with rest of tubing. Hooked up to 5 1/2" casing and pumped 30 sxs cement. Max. P.S.I. 500#. S.I.P. 275#. Hooked up to 8 5/8" casing and pumped 50 sxs MIDCON 2 cement with 2% C.C. and 100# hulls. Total 250 sxs cement used.

Remarks: Allied Cementing.

Condition of casing(in hole): GOOD BAD _____ Anhy.plug: YES NO _____
Bottom plug(in place): YES , CALC _____, NO _____ Dakota plug: YES , NO _____
Plugged through TUBING , CASING _____ Elevation: 2182 G.L.

I did [] / did not [] observe the plugging.

Dennis L. Hamel
(agent)

INVOICED
DATE JAN 13 1997
INV. NO. 47327