

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-20130-00-01
Spot: NENWSW Sec/Twnshp/Rge: 9-14S-19W
2310 feet from S Section Line, 4290 feet from E Section Line
Lease Name: VONFELDT Well #: 2
County: ELLIS Total Vertical Depth: 1036 feet

Operator License No.: 33069
Op Name: ENCORE OPERATING COMPANY
Address: P. O. BOX 27710
DENVER, CO 80227

PROD Size: 4.5 feet: 1036 150 SX CMT
SURF Size: 8.625 feet: 221 175 SX CMT

35.00

Well Type: SWD UIC Docket No: D21156.0 Date/Time to Plug: 11/12/2004 12:00 PM
Plug Co. License No.: 33346 Plug Co. Name: TR SERVICE AND RENTAL, INC.
Proposal Rcvd. from: ROLAND NYE Company: ENCORE OPERATING COMPANY Phone: (785) 737-3242

Proposed Plugging Method: Attempted to cement tubing in hole, assembly failed down hole, causing cement inside of tubing. Lost hole.
Ordered out 30 sxs 60/40 pozmix - 10% gel.
2 3/8" tubing cemented in 4 1/2" casing. PBTB 732' per wireline.
Rigged up and swabed dry to 732'.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/12/2004 1:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perfs:

Allied topped off 2 3/8" tubing with 15 sxs 60/40 pozmix - 10% gel.
Hooked up to backside and pumped 5 sxs cement.
Max. P.S.I. 500#.

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed

Richard Williams
(TECHNICIAN)

RECEIVED
NOV 17 2004
KCC WICHITA

NOV 15 2004


INVOICED
DATE 11-17-04
INV. NO. 2005060825

JAMES W. HERSHBERGER #2 VON FELDT 9-14-19W
NE NW SW

Contr. OMEGA DRLG Cty. ELLIS

Geol. Pool KRAUS

E. 2216 KB Cm. 9/25/67 Cp. 10/5/67 IP D&A/CONG



API 15-051-20,130

SMP Tops	Depth	Datum
TOP	3206	- 990
HEEB	3468	-1252
TOR	3491	-1275
LANS	3515	-1299
CONG CH	3820	-1604
RTD	3870	-1654

Csg. 8" 22/175 SX

NO LOG

DST 3674-94/1', 180' GIP,
1320' O&GCW, (20% OIL,
60% WTR) BHP 1207-1198#
/30", 102-918#

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS