

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-22402-00-00  
Spot: NESWNW Sec/Twnshp/Rge: 19-8S-22W  
3630 feet from S Section Line, 4290 feet from E Section Line  
Lease Name: QUINT B Well #: 4  
County: GRAHAM Total Vertical Depth: 3620 feet

Operator License No.: 6139  
Op Name: BOYER, JAY C.  
Address: PO BOX 511  
HAYS, KS 67601

PROD Size: 4.5 feet: 3618 w/125 sxs cmt  
SURF Size: 8.625 feet: 318 w/185 sxs cmt

4117<sup>65</sup>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/15/2004 2:00 PM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: HAROLD BELLERIVE Company: BOYER, JAY C. Phone: (785) 635-4531

Proposed Plugging Method: Ordered out 275 sxs 60/40 pozmix - 10% gel - 500# hulls.  
Casing leak. Fluid 300' from surface.  
Run tubing to 2200'+.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 11/15/2004 4:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran tubing to 2250'.  
Allied pumped 175 sxs 60/40 pozmix - 10% gel with 300# hulls - circulated cement.  
PTOH. Squeezed with 100 sxs cement with 200# hulls.  
Max. P.S.I. 500#. S.I.P. 200#.  
Hooked up to backside - instant 500#.

Perfs:

Top	Bot	Thru	Comments
3585	3588		
3554	3558		

RECEIVED  
NOV 17 2004  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY. EMERGENCY PLUG WHILE RIG OVER HOLE.

Plugged through: TBG

District: 04

100-

Signed Richard Williams  
(TECHNICIAN)

INVOICED

DATE 11-17-04

INV. NO. 2005060824

NOV 16 2004

JAY C. BOYER  
HAYS, KS 67601

19-08 -22W  
NE SW NW

#4 QUINT "B"

site: 1 S & 3/4 E OF HILL CITY, KS      city: GRAHAM      API 15-065-22402  
contr: WESTERN KANSAS DRILLING, INC      field: HILL CITY EAST  
geol: LAWRENCE E. GRAY

fr	spd	drig	card	last
date 09/03/87	date 09/05/87	comp 09/08/87	issued 12/30/87	revised 12/30/87


ELV: 2143 KB LOG  
tops.....depth/datum  
ANH.....1764 +379  
TOP.....3135 -992  
HEEB.....3159 -1016  
TOR.....3183 -1040  
LANS.....3398 -1255  
BKC.....3608 -1465  
RTD.....3620 -1477

IP status:  
OIL, P 8 BO & 18 BWPD, LKC 3554-3588 OA,  
CSG: 8-5/8" 318 / 135 SX, 4-1/2" 3618 / 125 SX  
NO CORES  
DST (1) 3530-3590 (LKC), MISRUN  
DST (2) 3524-3590 (LKC), / 30-45-45-60, REC 3' FREE  
OIL, 42' OCM (5% OIL, 95% M) ISIP 710# FSIP 600#  
IFP 54# -54# FFP 65# -65# IHP 1932# FHP 1877#  
MICT - CO, PF (KC) 3554-3558, 3585-3588, W / 4 SPF,  
AC 1500 GAL (15% NE), SWB LD, SO, RE-AC 2000 GAL  
(15% NE), SWB DWN, SO, SET 2" TBG AT 3579, POP, P  
8 BO & 18 BWPD, 9/25/87

COPYRIGHT 1987  
INDEPENDENT OIL & GAS SERVICE, INC.  
WICHITA, KANSAS

WICHITA  
BYE