

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-147-00871-00-00  
Spot: CNESESW Sec/Twnshp/Rge: 29-5S-20W  
990 feet from S Section Line, 2970 feet from W Section Line  
Lease/Unit Name: PINKERTON Well Number: 4  
County: PHILLIPS Total Vertical Depth: 3610 feet

Operator License No.: 30606  
Op Name: MURFIN DRILLING CO., INC.  
Address: 250 N. WATER, STE 300  
WICHITA, KS 67202

Conductor Pipe: Size feet:  
Surface Casing: Size 8.625 feet: 160 w/125 sxs cmt \$117.33  
Production: Size 5.5 feet: 3600 w/100 sxs cmt  
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 12/14/2001 10:00 AM

Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.

Proposal Rcvd. from: NIALL AVISON Company: MURFIN DRILLING CO., INC. Phone: (785) 483-0356

Proposed Plugging Method: Ordered 300 sxs Mid-Con - 2% gel with 1/4# flocele and 500# hulls.  
O.H. 3608' - 3615'. Perf at 1200' and 1770'.  
Ran tubing to 3425'. Casing bad.

Plugging Proposal Received By: PAT STAAB

WitnessType: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 12/14/2001 2:30 PM

KCC Agent: PAT STAAB

Actual Plugging Report:

Ran tubing in hole to 3400' - pumped 80 sxs cement with 300# hulls.  
Pulled tubing to 2000' - pumped 105 sxs with 200# hulls to circulate cement.  
Pulled tubing - tied onto casing with swedge and pumped 15 sxs cement.  
Max. P.S.I. 350#. S.I.P. 350#.  
Tied onto backside and pumped 50 sxs cement - backside went on small vacumm.  
Left cement set 1 1/2 hours - came back and pumped an additional 50 sxs backside with Max. P.S.I. 50#.

Remarks: SWIFT SERVICES, INC. - TICKET #3974.

Plugged through: TBG

District: 04

Signed

*Patricia Staab*

(TECHNICIAN)

RECEIVED

DEC 19 2001

KCC WICHITA

INVOICED

Form CP-2/3

DATE 12-20-01

INV. NO. 2002061079

DEC 17 2001

Cities Service Oil & Gas Co. Pinkerton 29-5-20W  
 NE SE SW  
 Contr. Phillips County  
 E 2200 Comm. 11-19-41 Comp. 12-10-41 IP Echo 2117

Tops	Depth	Datum	Casing
			8" 160
ANHY	1720		5" 3608
LANS	3351		
ARE	3595		
B SD	3603		
T.D.	3610		

INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS


1  
2  
3  
4  
5  
6  
7  
8  
9  
10  
11  
12  
13  
14  
15  
16  
17  
18  
19  
20  
21  
22  
23  
24  
25  
26  
27  
28  
29  
30  
31  
32  
33  
34  
35  
36  
37  
38  
39  
40  
41  
42  
43  
44  
45  
46  
47  
48  
49  
50  
51  
52  
53  
54  
55  
56  
57  
58  
59  
60  
61  
62  
63  
64  
65  
66  
67  
68  
69  
70  
71  
72  
73  
74  
75  
76  
77  
78  
79  
80  
81  
82  
83  
84  
85  
86  
87  
88  
89  
90  
91  
92  
93  
94  
95  
96  
97  
98  
99  
100