

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

15-147-00494-00-00

WELL PLUGGING APPLICATION FORM

(File One Copy)

Well was completed on

API NUMBER

1-17-49

(of this well)

6/88

(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Cities Service Oil & Gas Corporation OPERATORS LICENSE NO. 5447

ADDRESS 3545 N.W. 58th Street, Oklahoma City, OK 73112 PHONE # (405) 949-4400

LEASE (FARM) Vehige A WELL NO. 8 WELL LOCATION 2310' FWL COUNTY Phillips

SEC. 28 TWP. 5S RGE. 20 ~~(W)~~ (W) TOTAL DEPTH 3614' PLUG BACK TD --

Check One:

OIL WELL GAS WELL D & A SWD or INJ WELL DOCKET NO.

SURFACE CASING SIZE 8-5/8" SET AT 205' CEMENTED WITH 250 SACKS

CASING SIZE 5-1/2" SET AT 3614' CEMENTED WITH 150 SACKS

PERFORATED AT 3554-60'; 3566-72'

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Please refer to the attached plugging prognosis.

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? 1-17-49
(If not, explain)

Completed on

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN March 25, 1988

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

J. D. Hininger

PHONE # (913) 674-2182

ADDRESS Box 38, Hill City, KS 67642

PLUGGING CONTRACTOR Halliburton Oil Service LICENSE NO.

ADDRESS Oberlin, KS 67749 PHONE # (913) 475 - 2228

RECEIVED
STATE CORPORATION COMMISSION

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED:

Raymond Hui

(Operator or Agent)

MAR 15 1988

DATE:
CONSERVATION DIVISION
Wichita, Kansas

3-11-88

Raymond Hui

4



CITIES SERVICE OIL AND GAS CORPORATION

INTEROFFICE LETTER

15-147-00494-00-00

March 8, 1988
Wichita, Kansas

TO: Mr. M. D. Harrison
FROM: Mr. P. W. Pringle
SUBJECT: PLUGGING PROCEDURE.....VEHIGE "A" #8
2310' FSL-2310' FWL
SECTION 28-T5S-R20W
PHILLIPS COUNTY, KANSAS

WELL DATA:

8-5/8" SURFACE CASING AT 205' W/250 SX
5-1/2" PRODUCTION CASING AT 3614' W/150 SX
PERFORATIONS: 3554-60', 3566-72'
* PACKER STUCK DOWN HOLE AT 3531'

SHALLOW FORMATION DATA:

DAKOTA 705-1000'
CHEYENNE 1095-1175'
ANHYDRITE 1670-1705'

KCC APPROVED BY MR. DENNIS HAMEL (10/30/87)

1. Prior to plugging, contact Mr. Hamel at KCC district office #4, Hays, Kansas, phone number (913) 628-1200.
 2. Perforate above the anhydrite at 1660' w/4 SPF, perforate below the Dakota at 1050' w/3 SPF and perforate below surface casing seat at 220' w/3 SPF.
 3. Tie onto the 5-1/2" casing and fill the long pipe and casing annulus with cement and Hulls (Approx. 300 sx cement + 5 sx, Hulls and 75# Flocele).
 4. Let cement set 48 hours, check top of cement and cap well.
- NOTE: Cement calculations based on 65/35 cement w/10% gel, + 2% Econolite additive. Slurry volume 3.62 ft³/sx, blend ratio 23 gals water/sx. Add 1/4 pound Flocele/sx slurry.

PWP/mlf

RECEIVED
STATE CORPORATION COMMISSION

MAR 15 1988

CONSERVATION DIVISION
Wichita, Kansas



15-147-00494-00-00

Kansas Corporation Commission

MIKE HAYDEN
KEITH R. HENLEY
RICH KOWALEWSKI
MARGALEE WRIGHT
JUDITH MCCONNELL
FRANK A. CARO, JR.

GOVERNOR
CHAIRMAN
COMMISSIONER
COMMISSIONER
EXECUTIVE DIRECTOR
GENERAL COUNSEL

CONSERVATION DIVISION
SHARI M. FEIST, DIRECTOR
200 Colorado Derby Bldg.
202 W. 1st Street
Wichita, KS 67202-1286
(316) 263-3238

NOTICE

March 16, 1988

APR 16 '88

WELL PLUGGING NOTICE

EXPIRES

Vehige A #8
2310'FWL 2310'FSL
Sec. 28-05S-20W
Phillips County

Cities Service Oil & Gas Corporation
3545 NW 58th Street
Oklahoma City, OK 73112

Gentlemen:

This is your notice to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

Please contact the district office listed below to review your suggested method of plugging five days prior to plugging the well (KAR-82-3-113).

This notice is void after ninety (90) days from the above date.

Sincerely,

Shari Feist

Shari Feist
Director
State Corporation Commission

DISTRICT #4 2301 E. 13th, Hays, KS 67601 (913) 628-1200