

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 2/89
STATE CORPORATION COMMISSION
STATE OF KANSAS
MAY 11 1989
5-11-89
CONSERVATION DIVISION
Wichita, Kansas
6/89

13-147-00489-00-00

WELL PLUGGING APPLICATION FORM
(File One Copy)

API Number 06-18-42 (of this well). (This must be listed; if no API# was issued, please note drilling completion data.)

WELL OWNER/OPERATOR OXY USA INC. OPERATORS LICENSE NO. 5447

ADDRESS P. O. Box 26100 Oklahoma City, OK 73126-0100 PHONE # (405)749-2000
1650' FSL

LEASE/FARM Vehige "A" WELL NO. 3 WELL LOCATION 330' FWL COUNTY Phillips

SEC. 28 TWP. 5S RGE. 20 (~~N~~) or (W) Total Depth 3665' PLUG BACK TD 3633'

CHECK ONE:

OIL WELL X GAS WELL D & A SWD OR INJ WELL DOCKET NO.

SURFACE CASING SIZE 8 5/8" SET AT 165' CEMENTED WITH 125 SACKS

CASING SIZE 5 1/2" SET AT 3664' CEMENTED WITH 150 SACKS

CASING LINER: 4" FROM 3415-3633' CEMENTED WITH 40 SACKS

PERFORATED AT 3596-98'

CONDITION OF WELL: GOOD POOR CASING LEAK X JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Proposed plugging procedure is attached for KCC approval.

(If additional space is needed use back of form.)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? YES IS ACO-1 FILED? NO
(If not explain.)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN: 6-8-89 **

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:
Mr. J. D. Hininger PHONE # (913) 674-2182

ADDRESS OXY USA Inc., P. O. Box 38, Hill City, KS 67642

PLUGGING CONTRACTOR Ostrom Well Service Inc.* LICENSE NO.

ADDRESS RR 1, Box 368, Plainville, KS 67663 PHONE # (913) 434-2707

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.

SIGNED: Raymond Hininger
(Operator or Agent)

4

*Anticipated Service Co.

** APPROX. DATE

DATE: 5-10-1989



MEMORANDUM

OCCIDENTAL OIL AND GAS

15-147-00489-00-00

Wichita, Kansas
May 8, 1989

TO: Mr. M. D. Harrison

FROM: Mr. P. W. Pringle

SUBJECT: PLUGGING PROCEDURE..... VEHIGE "A" #3
1650' FSL - 330' FWL
SEC. 28-5S-20W
PHILLIPS CO., KS

WELL SPECS:

8 5/8" CASING @ 165' W/125 SX
5 1/2" CASING @ 3664' W/150 SX
4" LINER 3415-3633' W/40 SX
PERFORATIONS: 3596-98'
PBTB 3633'
FILL INSIDE CASING @ 3430'
CASING LEAK @ 2463'

SHALLOW FORMATION DATA:

DAKOTA 705-1000'
CHEYENNE 1095-1175'
ANHYDRITE 1715-1740'

-
1. Prior to plugging, obtain approval of project from the KCC Field Office #4, Hays, KS (913) 628-1200.
 2. Perforate at 1700' and 1050' using 4 SPF/interval.
 3. Tie onto the 5 1/2" casing and pump in the hole approximately 306 sx 65/35 Pozmix + 8% gel and hulls to surface. Pressure up on casing. (Have 500# hulls at location)
 4. If circulation was not established. Tie onto the 8 5/8" casing and pump 100 sx (same) cement down the annulus.
 5. Let slurry set 48 hrs., check TOC and cap the well.

State of Kansas



15-147-00489-00-00

Kansas Corporation Commission

MIKE HAYDEN GOVERNOR
KEITH R. HENLEY CHAIRMAN
RICH KOWALEWSKI COMMISSIONER
MARGALEE WRIGHT COMMISSIONER
JUDITH McCONNELL EXECUTIVE DIRECTOR
FRANK A. CARO, JR. GENERAL COUNSEL

THIS NOTICE

AUG 15 1989

EXPIRES

CONSERVATION DIVISION
SHARI FEIST ALBRECHT, DIRECTOR
200 Colorado Derby Bldg.
202 W. 1st Street
Wichita, KS 67202-1286
(316) 263-3238

May 15, 1989

NOTICE OF RECEIPT OF
WELL PLUGGING APPLICATION

OXY USA, Inc.
P. O. Box 26100
Oklahoma City, OK 73126-0100

Vehige "A" #3
1650'FSL 330'FWL
Sec. 28-05S-20W
Phillips County

Gentlemen:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office to review your proposed plugging method at least five (5) days before plugging the well.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. The CP-1 is simply reviewed to determine compliance with plugging rules and regulations.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

Shari Feist Albrecht
Shari Feist Albrecht
Director

District: #4 2301 E. 13th
Hays, KS 67601
(913) 628-1200