

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

FORM CP-1  
Rev. 2/89

RECEIVED  
STATE CORPORATION COMMISSION

JUN 11 1990  
6-11-90  
CONSERVATION DIVISION  
Wichita, Kansas

WELL PLUGGING APPLICATION FORM  
(File One Copy)

API Number 7-3-43 (of this well). (This must be listed; if no API# was issued, please note drilling completion data.)

WELL OWNER/OPERATOR OXY USA INC. OPERATORS LICENSE NO. 5447 6/9/

ADDRESS P. O. Box 26100 Oklahoma City, OK 73126-0100 PHONE # (405) 749-2000  
1650' FSL

LEASE/FARM Reese "E" WELL NO. 4 WELL LOCATION 2310' FEL COUNTY Phillips

SEC. 28 TWP. 5S RGE. 20 ~~(S)~~ or (W) Total Depth 3630' PLUG BACK TD 3598'

CHECK ONE:

OIL WELL X GAS WELL      D & A      SWD OR INJ WELL      DOCKET NO.     

SURFACE CASING SIZE 8-5/8" SET AT 153' CEMENTED WITH 67 SACKS

CASING SIZE 5-1/2" SET AT 3630' CEMENTED WITH 150 SACKS

PERFORATED AT 3104-3578' (9 sets)

CONDITION OF WELL: GOOD X POOR      CASING LEAK      JUNK IN HOLE     

PROPOSED METHOD OF PLUGGING Procedure is attached for KCC review & approval.

(If additional space is needed use back of form.)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? No  
(If not explain.)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN: 7-11-90

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq  
AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

J. D. Hininger PHONE # (913) 674-2182  
ADDRESS OXY USA INC., P.O. Box 38, Hill City, Kansas 67642

PLUGGING CONTRACTOR J. W. Gibson Well Service  
ADDRESS Logan, Kansas 67646

LICENSE NO. 5866 8/90  
PHONE # (913) 689-7573

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR  
OR AGENT.

SIGNED: Philip W. Pringle  
(Operator or Agent)

DATE: June 11, 1990

(4)



15-147-00480-00-00

**MEMORANDUM**  
OCCIDENTAL OIL AND GAS

Wichita, Kansas  
June 11, 1990

TO: Mr. M. D. Harrison

FROM: Philip W. Pringle

SUBJECT: PROCEDURE TO PLUG & ABANDON.....REESE "E" #4  
1650' FSL - 2310' FEL  
SEC 28-5S-20W  
PHILLIPS COUNTY, KANSAS

Well Data

8-5/8" surface casing @ 153' w/ 67 sx  
5-1/2" production casing @ 3630' w/ 150 sx  
Perforations: 3104-3578' (9 sets)  
PBSD = 3598'

Shallow Formation Depths

Dakota	705-995'
Cheyenne	1075'
Anhydrite	1665'

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 11 1990  
CONSERVATION DIVISION  
Wichita, Kansas  
6-11-90

1. Contact the KCC District Office #4, Hays, KS, (913) 628-1200, to obtain final approval of this plugging procedure.
2. Run perforating gun and fire 4 SPF at 1655' and 1045'.
3. Run 2-3/8" workstring to bottom, and spot 75 sx common cement w/ 2% CC. Pull tubing and fill 5-1/2" casing to surface w/ approximately 300 sx 65/35 cement w/ 6% gel. Use hulls as needed.
4. Tie onto the 5-1/2" and attempt to circulate cement. If needed tie onto the 8-5/8" and fill the annulus to surface w/ 100 sx same cement.
5. Let cement set 48 hours, check TOC and cap well.

PWP/cd

15-147-90480-00-00

## WELL RECORD

Company Cities Service Oil Co. Well No. 4 Farm Reese "E"  
 Location 990' South and 330' East of Center Sec. 28 T. 5 R. 20W  
 Elevation 2153 County Phillips State Kansas  
 Drig. Comm. June 23, 1943 Contractor R. W. Rine Drilling Co.  
 Drig. Comp. July 3, 1943 Acid None  
 T. D. 3630' Initial Prod. Kohometer: 2161 oil, no water, 24 hrs.

CASING RECORD:

8-5/8"  $\odot$  153' cem. 67 sz cement  
 5-1/2"  $\odot$  3630' cem. 150 sz Ash Grove

FORMATION RECORD:

surface	0-70
slate	158
sand & shale	565
shale & sand	1665
anhydrite	1702
shale	1850
shale & shells	2850
shale & lime	3130
lime	3632

3632 Rot. TD = 3630' ELM

Ran Schlumberger.

Corr. Top Arbuckle	3539'
Corr. Top Reagan	3593'
Corr. Total Depth	3630'

July 9, 1943: Perf. 24 shots 3575-78;  
 100' fluid in  $\frac{1}{4}$  hr.  
 200' fluid in  $\frac{3}{4}$  hr.  
 1400' oil in  $1\frac{1}{2}$  hrs.  
 2100' oil in 1- $\frac{3}{4}$  hrs.  
 2675' oil in 4- $\frac{3}{4}$  hrs.

Perf. penetration Arbuckle, 39'.

Slope Test (Acid Bottle):	500'	OK
	1000'	OK
	1500'	OK
	2000'	OK
	2500'	OK
	3000'	OK

RECEIVED  
CONSERVATION DIVISION

JUN 11 1990

CONSERVATION DIVISION  
Wichita, Kansas

6-11-90



MIKE HAYDEN  
KEITH R. HENLEY  
RICH KOWALEWSKI  
MARGALEE WRIGHT  
JUDITH McCONNELL  
FRANK A. CARO, JR.

GOVERNOR  
CHAIRMAN  
COMMISSIONER  
COMMISSIONER  
EXECUTIVE DIRECTOR  
GENERAL COUNSEL

Kansas Corporation Commission

CONSERVATION DIVISION  
SHARI FEIST ALBRECHT, DIRECTOR  
200 Colorado Derby Bldg.  
202 W. 1st Street  
Wichita, KS 67202-1286  
(316) 263-3238

THIS NOTICE

SEP 11 1990

EXPIRES

June 11, 1990

NOTICE OF RECEIPT OF  
WELL PLUGGING APPLICATION

OXY USA INC.  
P.O. Box 26100  
Oklahoma City, Ok 73126-0100

Reese "E" 4  
1650' FSL-2310' FEL  
Sec. 28-05-20W  
Phillips County

Gentlemen:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office to review your proposed plugging method at least five (5) days before plugging the well.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. The CP-1 is simply reviewed to determine compliance with plugging rules and regulations.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

*Shari Feist Albrecht*  
Shari Feist Albrecht  
Director

District: #4 2301 E. 13th  
Hays, KS 67601  
(913) 628-1200