

State of Kansas



15-023-20002-00-00

ROBERT B. DOCKING Governor  
 DALE E. SAFFELS Chairman  
 JULES V. DOTY Commissioner  
 JAMES O. GREENLEAF Commissioner  
 RAYMOND B. HARVEY Secretary  
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

212 N. Market

WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

SEP 16 1968

CONSERVATION DIVISION  
Wichita, Kansas

9-16-68

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Al Thompson of Mack Oil Company has this

date requested permission to plug the following described well:

Mr. Thompson guarantees payment of the plugging fee.

Operator's full Name: Mack Oil Company,

Complete Address: 812 Union Center Building, Wichita, Kansas.

Lease Name: Hart Well No. 1

Location: CNW-SE-SE Sec. 23 Twp. 4 Rge. (E)(W) 42

County: Cheyenne Total Depth 5207 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Thompson was instructed to plug the well as follows:

382'--8 5/8" Surface casing, cement circulated with 325 Sx.

Top of Dakota section @ 2250'.

Circulate hole with heavy mud. Pull DP to 2475' and displace 100 Sx.  
cement thru DP. Pull DP to 395' and displace 25 Sx. cement thru DP.  
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom  
of cellar.

Very truly yours,

W. D. Nichols  
Conservation Division Agent