



15-147-20139-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
OCT 18 1971
CONSERVATION DIVISION
Wichita, Kansas
10-18-71

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Trarbach of Sage Drlg. has this
date requested permission to plug the following described well:

Mr. Tarabach guarantees payment of the plugging fee.

Operator's full Name: Lebem, et al

Complete Address: 200 W. Douglas Wichita, Ks.

Lease Name: Wiltrout Well No. 1

Location: SW SE SW Sec. 2 Twp. 5 Rge. (E)(W) 20

County: Phillips Total Depth 3482' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Tarabach was instructed to plug the well as follows:
Gun pits, circulate heavy mud, set cementing plug at 800' and displace
70 sk cmt thru drill pipe. Heavy mud to 240' set cementing plug and
displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing
plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Geo. F. Massey
Conservation Division Agent