



18-147-20071-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

OCT 25 1972

CONSERVATION DIVISION
Wichita, Kansas

10-25-72

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Albert Unruh of Southwest Csg. Pulling, Inc., has this date requested permission to plug the following described well:

Mr. Unruh guarantees payment of the plugging fee.

Operator's full Name: Leland Baird,

Complete Address: Logan, Kansas.

Lease Name: States Well No. 1

Location: SE-NE-NW Sec. 18 Twp. 5 Rge. (E)(W) 20

County: Phillips Total Depth 3520' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Unruh was instructed to plug the well as follows:

217'--8 5/8" Surface casing, cement circulated with 135 Sx.

3519'--1 1/2" Production casing cemented on bottom with 200 Sx. Top of cement @ 2140'. Well plugged back to 3288'. Top perforations 3262' to 3264'.

Sand well back to 3250' and set 5 Sx. cement with dump bailer. Pull 1 1/2" casing and squeeze well with 5 sacks hulls, 30 sacks gel and 150 Cu. Ft. cement, staged.

Very truly yours,

H. L. Nichols
Conservation Division Agent