



15-147-20110-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

RECEIVED
STATE CORPORATION COMMISSION

OCT 27 1970

CONSERVATION DIVISION
Wichita, Kansas

10-27-70

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Draper of Dreiling Drlg. has this
date requested permission to plug the following described well:

Mr. Draper guarantees payment of the plugging fee.

Operator's full Name: H. B. Mabee Co.

Complete Address: Box 94718 Oklahoma City, Okla.

Lease Name: Lamb Well No. 1

Location: 100' SW of SE NE SW 16 Twp. 5 Rge. (E)(W) 20

County: Phillips Total Depth 3595 Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Draper was instructed to plug the well as follows:
Gun pits, circulate heavy mud, set cementing plug at 1100' and displace
100 sk cmt thru drill pipe. Heavy mud to 250' set cementing plug and
displace 25 sk cmt thru drill pipe. Heavy mud to 40' set cementing plug
1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Leo J. Murray
Conservation Division Agent