



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

RECEIVED
STATE CORPORATION COMMISSION
MAR 8 1971
CONSERVATION DIVISION
Wichita, Kansas

3-8-71

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Gustus of Leben Drlg. has this

date requested permission to plug the following described well:

Mr. Gustus guarantees payment of the plugging fee.

Operator's full Name: Leben Et al

Complete Address: 200 W. Douglas Wichita, ks/

Lease Name: Langan Well No. 1

Location: NE NW NE Sec. 2 Twp. 5 Rge. (E)(W) 20

County: Phillips Total Depth 3400' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Gustus was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 600' and displace
70 sk cmt thru drill pipe. Heavy mud to 230' set cementing plug and
displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing
plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Leo P. Messer
Conservation Division Agent