



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian WICHITA, KANSAS 67217

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

10-9-73 RECEIVED STATE CORPORATION COMMISSION

OCT 9 1973 CONSERVATION DIVISION Wichita, Kansas

J. Lewis Brock Administrator 500 Insurance Building Wichita, Kansas 67202

Dear Sir:

Mr. Albert Unruh of Southwest Casing Pulling Co., has this date requested permission to plug the following described well:

Mr. Unruh guarantees payment of the plugging fee.

Operator's full Name: Bankoff Oil Company,

Complete Address: 1119 Sherman, Great Bend, Kansas.

Lease Name: Hill Well No. B-1

Location: SW-SW-NW Sec. 2 Twp. 5 Rge. (E)(W) 20

County: Phillips Total Depth 3406 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Unruh was instructed to plug the well as follows:

198'--8 5/8" Surface casing, cement circulated with 125 Sx. 3403'--5 3/8" Production casing cemented on bottom with 125 Sx. No plug-back indicated. Top perforations from 3155' to 3158'.

Sand well back to 3100' and set 5 Sx. cement with dump bailer. Pull 5 1/2" casing and squeeze well with 5 sacks hulls, , 35 sacks gel and 125 Sx. cement, staged.

Very truly yours,

M. G. Dzuchala

Conservation Division Agent