



15-147-00457-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 20 1970  
CONSERVATION DIVISION  
Wichita, Kansas  
8-20-70

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Albert Unruh of South West Csg. Pulling Co., has this date requested permission to plug the following described well:

Mr. Unruh guarantees payment of the plugging fee.

Operator's full Name: Bankoff Oil Company,

Complete Address: Drawer #2479, Tulsa, Oklahoma.

Lease Name: Perry Well No. 2

Location: SE-SE-SE Sec. 3 Twp. 5 Rge. (E)(W)20

County: Phillips Total Depth 3415 Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Unruh was instructed to plug the well as follows:

191'--10 3/4" Surface casing, cement circulated.  
3411'--5 1/2" Production casing, cemented on bottom with 150 Sx. Well plugged back to 3189'. Top perforations from 3189' to 3160'.

Sand well back to 3150' and set 5 Sx. cement with dump bailer. Pull 5 1/2" casing and squeeze well with 5 sacks hulls, 30 sacks gel and 180 Sx. cement staged.

Very truly yours,

N. L. Nichols  
Conservation Division Agent