

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-053-20881-00-00
Spot: NWSWSE Sec/Twnshp/Rge: 30-17S-10W
990 feet from S Section Line, 2310 feet from E Section Line
Lease Name: HICKEL Well #: 5
County: ELLSWORTH Total Vertical Depth: 3286 feet

Operator License No.: 6039
Op Name: L.D. DRILLING, INC.
Address: RR 1 BOX 183B 7 SW 26TH AVENUE
GREAT BEND, KS 67530

PROD Size: 5.5 feet: 3279 150 SX CMT
SURF Size: 8.625 feet: 302 165 SX CMT

#106⁸⁰

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/25/2004 10:45 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Revd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 562-8088

Proposed Plugging Method: See actual report.

RECEIVED
KCC DISTRICT #2
NOV 4 - 2004
WICHITA, KS

Plugging Proposal Received By: VIRGIL CLOTHIER WitnessType: NONE
Date/Time Plugging Completed: 10/25/2004 12:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Perfs:

Sanded to 3230' and put 5 sacks of cement on top. Cut off 5-1/2" casing at 2005'. Pulled to 1300' and pumped 35 sacks of cement. Pulled casing to 950' and pumped 35 sacks of cement. Pulled casing to 360' and circulated cement to surface.

60/40 posmix with 4% gel

Copeland Cement #25079

RECEIVED
NOV 19 2004
KCC WICHITA

Remarks:

Plugged through: CSG

District: 02

Signed

Virgil Clothier
(TECHNICIAN)

INVOICED

DATE 11-22-04

INV. NO. 2005060838