

6 010672

6-615-147-00489-00-00

Old Well

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-

SW NW SW _____, SEC. 28, T. 5 S, R. 20 W/E

1650 feet from S section line

4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5447

Operator: Oxy USA Inc.

Name & Address: Box 26100

Oklahoma City, Ok.

Lease Name Vehicle Well # A-3

County Phillips

119.08

Well Total Depth 3664 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 165

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated Oxy USA

Plugging Contractor _____ License Number 5447

Address Same

Company to plug at: Hour: 9:30AM Day: 6 Month: June Year: 19 89

Plugging proposal received from Gene Hutchison

(company name) Oxy USA (phone) _____

were: Order 450 sks 65/35 pzo 8% gel 2 sks f.c. 500# hulls.

Perf at 1730' and 1090' 5 1/2" casing at 3664' 4" liner 3415' - 3633' w/40 sks cement. Perf 3596' 98' casing leak at 2463'. Anhydrite 1715' - 1740'. Elev. 2186' Dakota 1400' 786' = 1086

Plugging Proposal Received by D. F. B. (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: _____ Day: 6 Month: June Year: 19 89

ACTUAL PLUGGING REPORT Pumped down 5 1/2" casing 300 sks cement w/250# hulls. Max 600# pres. Close 400#. Pumped down 8 5/8" 150 sks w/2 sks f.c. and 250# hulls. Max 900# close 400#.

Remarks: Allied Cement Co. (If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

DATE 6-14-89

INV. NO. 25064

Signed Dale F. Balchazor