

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-147-00488-00-00

Spot: NWSWSW

Sec/Twnshp/Rge: 28-5S-20W

990 feet from S Section Line, 990 feet from W Section Line

Lease/Unit Name: VEHIGE A

Well Number: 2

County: PHILLIPS

Total Vertical Depth: 3595 feet

Operator License No.: 30606

Op Name: MURFIN DRILLING CO., INC.

Address: 250 N. WATER, STE 300  
WICHITA, KS 67202

Conductor Pipe: Size

feet:

Surface Casing: Size 8.625

feet: 150

125 SX CMT

Production: Size 5.5

feet: 3584

100 SX CMT

Liner: Size

feet:

\$116.84

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 12/13/2001 9:30 AM

Plug Co. License No.: 30606

Plug Co. Name: MURFIN DRILLING CO., INC.

Proposal Rcvd. from: NIALL AVISON

Company: MURFIN DRILLING CO., INC.

Phone: (785) 683-0356

Proposed  
Plugging  
Method:

Ordered out 250 sxs Swift Multi Density Cement with 500# hulls.  
5 1/2" set at 3584'. O.H. Completion 3584' - 3595'. PBTD 3575'.  
Perforated anhydrite at 1730' 2 holes. Dakota at 1160' 2 holes.

Plugging Proposal Received By: RICHARD WILLIAMS

Witness Type: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 12/13/2001 2:30 PM

KCC Agent: RICHARD WILLIAMS

**Actual Plugging Report:**

Rigged up company tools. Ran 2 3/8" tubing to 3543'.  
Swift Services pumped 80 sxs with 300# hulls.  
Pulled to 1800'.  
Swift Services pumped 90 sxs with 200# hulls. Cement circulated.  
Hooked up to backside - pumped 15 sxs cement - circulated out 5 1/2" casing. Shut in.  
Hooked back to 5 1/2" casing and pumped 65 sxs cement.  
Max. P.S.I. 100#. S.I.P. 100#.

Remarks: SWIFT SERVICES, INC.

Plugged through: TBG

District: 04

Signed

Richard Williams

(TECHNICIAN)

RECEIVED

DEC 19 2001

KCC WICHITA

DEC 17 2001

INVOICED

DATE 12-20-01

INV. NO. 2002061079

Form CP-2/3