

15-147-00487-00-00

4-041608

8-30

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15- - 6-25-41

SW SW SW /4 SEC. 28, 05 S, 20 W
330 feet from S section line
330 feet from E section line

Operator license# 5447 Lease Vehige 'A' well # 1

Operator: OXY USA, Inc. County Phillips

Address: 110 S. Main Well total depth 3654 feet
Suite #800 Conductor Pipe: 0 inch @ 0 feet
Wichita, Kansas 67202 Surface pipe 8 5/8 Inch @ 166 feet
w/125 sxs.

118.76

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Halliburton Cementing License#

Address: Oberlin, Kansas

Company to plug at: Hour: 8:00A.M. Day: 30 Month: August Year: 94

Plugging proposal received from: Jim Nowell

Company: OXY USA, Inc. Phone:

Were: 5 1/2" casing set @ 3654' w/125 sxs. cmt. Perf. @ 3568' - 3654'.
Anhy. @ 1750' - Dakota @ 1090' - C.I.B.P. @ 3500'.
Ordered 300 sxs. 60/40 pozmix - 10% gel with 1/4# F.C. plus 500# hulls.

Plugging Proposal Received by: Dennis L. Hamel
Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 12:00P.M., Day: 30, Month: August, Year: 94

Actual plugging report: R.I.H. with tubing to 3400'. Spotted 60 sxs.
cement with 200# hulls. Pulled to 2400' - spotted 75 sxs. cement with
100# hulls. Pulled to 1050' - spotted 60 sxs. cement with 100# hulls.
Cement circulated at surface. Pulled tubing and squeezed casing with
55 sxs. cement. Max. 300#. 8 5/8" S.P. Pumped in 50 sxs. cement
with 100# hulls.

Remarks:
Condition of casing(in hole): GOOD X BAD Anhy. plug: YES X NO
Bottom plug(in place): YES X, CALC , NO Dakota plug: YES X, NO
Plugged through TUBING X, CASING . Elevation: GL

9-14-94
RECEIVED
STATE CORPORATION COMMISSION

SEP 14 1994

I did X did not [] observe the plugging.

Dennis L. Hamel
DIVISION
agent

DATE 9-26-94
INV. NO. 4125-7