

4-031717

7-12

201  
R

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-147-20,540-00-00

SE SE NW /4 SEC. 31, 05 S, 20 W  
2970 feet from S section line  
2970 feet from E section line

Operator license# 5447

Lease Veeh "A" well # 15

Operator: OXY USA, Inc.

County Phillips

Address: 110 S. Main  
#800  
Wichita, Kansas 67202

Well total depth 3731 feet <sup>121.25</sup>  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 388 feet

Aband. oil well     , Gas well     , Input well     , SWD     , D & A X

Plugging contractor: Abercrombie Drilling License# 5422

Address: Wichita, Kansas 67202

Company to plug at: Hour: P.M. Day: 12 Month: July Year: 92

Plugging proposal received from: Jim

Company: OXY USA, Inc. Phone:                     

Were: Order 190 sx. 60/40 pozmix - 6% gel. - 3% c.c.  
Halliburton Cement Company.  
8 5/8" set @ 270 sx. cwc.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All[      ], Part[      ], None[ X ]

Completed: Hour: 8:15P.M., Day: 12, Month: July, Year: 92

Actual plugging report: Spot cement plugs with drill pipe.  
1st. plug @ 1750' w/25 sx.  
2nd. plug @ 1060' w/100 sx.  
3rd. plug @ 425' w/40 sx.  
4th. plug @ 40' w/10 sx. W.P.  
Circulate 15 sx. in Rathole.

Remarks: Anhy. 1750' - 80'.

Condition of casing(in hole): GOOD      BAD      Anhy. plug: YES X NO     

Bottom plug(in place): YES X, CALC     , NO      Dakota plug: YES X, NO     

Plugged through TUBING     , CASING X. Elevation: 2188 GL     

I did      / did not [ X ] observe the plugging.

Carl Goodrow CONSERVATION DIVISION  
WICHITA, KANSAS

DATE 8-4-92

(agent)

INV. NO. 35855

Form CP-2/3

RECEIVED

JUL 29 1992

7-29-92