

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-053-20831-00-00
Spot: SWSWSE Sec/Twnshp/Rge: 30-17S-10W
330 feet from S Section Line, 2310 feet from E Section Line
Lease Name: HICKEL Well #: 4
County: ELLSWORTH Total Vertical Depth: 3300 feet

Operator License No.: 6039
Op Name: L.D. DRILLING, INC.
Address: RR 1 BOX 183B 7 SW 26TH AVENUE
GREAT BEND, KS 67530

PROD Size: 4.5 feet: 3292 NOT AVAILABLE
SURF Size: 8.625 feet: 255 NOT AVAILABLE

#107²⁵

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/26/2004 12:15 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 562-8088

Proposed Plugging Method: See actual report.

RECEIVED
KCC DISTRICT #2
NOV 4 - 2004
WICHITA, KS

Plugging Proposal Received By: VIRGIL CLOTHIER WitnessType: PARTIAL
Date/Time Plugging Completed: 10/26/2004 2:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Perfs:

Sanded to 3240' and put 4 sacks of cement on top. Cut off 4-1/2" casing at 1527'. Pulled to 1300' and pumped 35 sacks of cement. Pulled casing to 950' and pumped 35 sacks of cement. Pulled casing to 310' and circulated cement to surface.

60/40 posmix with 4% gel.

Copeland Cement #25080

RECEIVED
NOV 19 2004
KCC WICHITA

Remarks:
Plugged through: CSG

District: 02

Signed Virgil Clothier
(TECHNICIAN)

INVOICED
DATE 11.22.04
INV. NO. 2005060838