

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-155-21411-00-00  
Spot: NWSE Sec/Twnshp/Rge: 11-25S-9W  
1980 feet from S Section Line, 1980 feet from E Section Line  
Lease Name: BIGGERSTAFF Well #: 5-11  
County: RENO Total Vertical Depth: 4000 feet

Operator License No.: 3911  
Op Name: RAMA OPERATING CO., INC.  
Address: 101 S. MAIN  
STAFFORD, KS 67578

PROD Size: 5.5 feet: 3980 100 SX CMT  
SURF Size: 8.625 feet: 193 175 SX CMT

*# 130<sup>00</sup>*

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/05/2004 11:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 562-8088

Proposed Plugging Method: See actual report.

RECEIVED  
KCC DISTRICT #2  
NOV 10 2004  
WICHITA, KS

Plugging Proposal Received By: VIRGIL CLOTHIER WitnessType: PARTIAL  
Date/Time Plugging Completed: 11/05/2004 1:50 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Perfs:

Sanded to 3930' and put 5 sacks of cement on top. Shot off casing at 1900'. Pulled to 1400' and pumped 35 sacks of cement with 200 lbs of cotton hulls. Pulled casing to 800' and pumped 35 sacks of cement with 150 lbs of cotton hulls. Pulled casing to 250' and circulated cement to surface.

205 sxs 60/40 posmix with 4% gel

Copeland Cementing #25128

RECEIVED  
NOV 19 2004  
KCC WICHITA

Remarks:

Plugged through: CSG

District: 02

Signed Virgil Clothier  
(TECHNICIAN)

INVOICED  
DATE 11-22-04  
INV. NO. 2005060839