

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-191-22015-00-00  
Spot: S2NESESW Sec/Twnshp/Rge: 7-30S-2W  
800 feet from S Section Line, 2970 feet from E Section Line  
Lease Name: SUSIE DUNCAN Well #: 2  
County: SUMNER Total Vertical Depth: 4098 feet

Operator License No.: 5822  
Op Name: VAL ENERGY, INC.  
Address: PO BOX 116  
WICHITA, KS 67201

CIBP Size: feet: 3230  
PROD Size: 5.5 feet: 3310 100 SX CMT  
SURF Size: 8.625 feet: 330 200 SX CMT

#133<sup>19</sup>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/02/2004 10:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 257-2719

Proposed Plugging Method: SAND BACK 50' OVER PERFS, SPOT 10 SX PLUG, SHOOT OFF PIPE AND PULL, SPOT 35 SX, PLUG AT 525' AND CEMENT TO SURFACE.

RECEIVED  
KCC DISTRICT #2  
NOV 9 - 2004

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL WICHITA, KS  
Date/Time Plugging Completed: 11/02/2004 12:00 PM KCC Agent: DAVE WERTZ

Actual Plugging Report:

Sanded back to 3140' and capped with 5 sacks of cement. Shot off 5-1/2" at 2635'. Pulled to 600' and spotted 35 sacks of cement. Pulled to 400' and spotted 35 sacks of cement. Pulled to 250' and circulated to surface.

119 sxs 60/40 posmix with 4% gel

Jinted #5767

Perfs:

Top	Bot	Thru	Comments
3235	3237		
3207	3210		

RECEIVED  
NOV 19 2004  
KCC WICHITA

Remarks:

Plugged through: CSG

District: 02

Signed

David Wertz

(TECHNICIAN)

INVOICED  
DATE 11.22.04  
NO. 2005060840